

**Consent Notice Pursuant to Section 221  
Resource Management Act 1991**

File Ref: S/B 8508

**IN THE MATTER OF:**

1-70, 73-84, and 123-124 of Deposited  
Plan 367979

**A N D**

**IN THE MATTER OF:**

Subdivision Consent pursuant to  
Sections 108, 220 and 221 of the  
Resource Management Act 1991.

**PURSUANT** to Section 252(1)(a) of the Local Government Act 1974, I, STEVE HILL, Authorised Officer of the Western Bay of Plenty District Council, hereby certify that the following conditions of consent were imposed on the subdivision consent for Pt Allotments 52, 52A, 53, 53A, 54, 54A, 55 and 91, 91A Te Puna Parish, Part DP 3254 and Pt Lot 6 DP 12835.

**1. Building Line Restrictions and Geotechnical Recommendations**

The following building line and geotech conditions apply to Lots 1-7, 12, 30-45, 54, 57-61, 65-70, 73-78, 83 - 84, and 123.

*A10.3 THAT a building line restriction be determined in accordance with the recommendations of the geotechnical report prepared by Foundation Engineering dated 16 December 1999 or subsequent geotechnical reports prepared by a registered engineer suitably experienced to the satisfaction of the Principal Administrative Officer and be shown on the Land Transfer plan and registered against the certificates of title of the relevant lots.*

*A10.4 THAT a consent notice pursuant to Section 221 of the Resource Management Act 1991 be issued against the titles of allotments that are subject to building restriction lines or any other geotechnical constraints. Those allotments shall be specified in the Geotechnical completion report to be submitted with the Section 224 application.*

[Note: The final geotechnical completion report and information are provided in the Tonkin and Taylor letters and attachments dated 12 May 2006 and 12 April 2006 (Ref 60619), the Amended Covenant Schedule date stamped 9 May 2006, and the Tonkin and Taylor Report for Lynley Park Subdivision, Omokoroa Stage 1A - Geotechnical Report dated February 2006 (Ref 60619)]

The following geotech condition applies to all residential lots created on DP 367979 and forms part of the 'Statement of Professional Opinion as to the Geotechnical Suitability of Land for Building' prepared by Tonkin and Taylor and dated 22 February 2006.

*The areas shown in my report dated February 2006 of each new allotment or on the development site are suitable for erection thereon of the building types appropriate to the zoning of the land, provided that: foundation inspections by the regulatory authorities and a suitably qualified engineer should be carried out during construction, and construction is in accordance with NZS 3604:1999 and related documents; building restriction lines indicate those areas where specific design is required.*

## **2. Landscaping and Amenity Planting**

The following landscaping condition applies to Lots 30-45 and Lot 54 and is shown on the DPS plan 'C1 to C17'.

A4.3 *THAT any surplus land not required to satisfy the foregoing conditions 4.1 and 4.2 shall be incorporated into the adjoining lots and be subject to covenants registered on the certificates of titles of such lots restricting and preserving the land for landscape and amenity planting in accordance with the recommendation contained in the CGC Ltd report dated 30 November 2000 and in the evidence presented at the hearing by David Clayton-Greene.*


[Note: The landscaping plan approved for the escarpment is the CGC Plan dated 31 August 2005 Sheet 1 and 2 as amended to include the 'General Notes'. The planting as shown on this plan must be maintained by the landowner at all times unless prior written approval is obtained from Western Bay of Plenty District Council to modify or remove the planting. Any planting will not however be permitted which is in conflict with condition A15.7 of consent (refer clause 6 below).]

## **3. Reserve Fencing Restrictions**

The following fencing condition applies to Lots 30-45, 54-56, 15-16, and 18-20.

A4.8 *THAT a consent notice pursuant to Section 221 of the Resource Management Act 1991 be issued against the titles of all lots adjoining Council reserves to the effect that the construction of the fences on the common boundary are at the expense of the respective landowners or occupiers.*

## **4. Buttress Drains**

The following buttress drain condition applies to Lots 30-31, 34- 35, 39, 40, 42-45, 54 and ~~124~~. 

A15.7 *THAT no trees be planted within a horizontal distance of 5.0 metres from the centre line of the buttress drains as shown on the attached CKL drawing Subsoil Drainage (Ref D1176 Rev AB1) Pages 2 -5, unless prior written approval from the Western Bay of Plenty District Council is obtained. Trees will only be permitted which have a shallow root structure so as to avoid any detrimental affect on the Buttress Drains. The landscaping measures as required by conditions A4.3 of consent are to be maintained at all times.*

**5. Reserve Linkage Lot**

A4.9 *THAT Lot 123 be sold to the Council and a consent notice registered on the certificate of title for the lot restricting the use of the land to the provision of a linkage to other land on the southern side of the railway line unless alternative provision is made for such linkage.*

Dated at Tauranga this 21<sup>st</sup> day of June 2006



\_\_\_\_\_  
Authorised Officer



T&T job no: 60619  
12 May 2006

Durham Property Investments  
PO Box 15197  
Dyonsdale  
Hamilton

Attention: Philip Palmer

Dear Philip

**Lynley Park Subdivision, Omokoroa  
Lot 123 Geotechnical Completion Report**

Lot 123 has now been included as part of the Stage 1a completion of Lynley Park. This letter is the geotechnical completion report for Lot 123 on the above subdivision and should be considered an addendum to the completion report for Stage 1a. Detail of the background on the earthworks for this subdivision are included in the Tonkin & Taylor Ltd report *Lynley Park Subdivision, Omokoroa - Stage 1a Completion Report and dated February 2006*.


This letter also includes the Section 224 Certification Statement from the Western Bay of Plenty District Council Proposed Code of Practice for Subdivision Development, as requested by WBOPDC.

Enclosed with this letter are;

- Summary Lot table for Lot 123
- Site test location plan Figure 3 rev1 showing lot location and cut/fill depths
- Statement of Professional Opinion for Lot 123
- Section 224 Certification Statement

Please contact the undersigned if you have any queries regarding this report.

Yours sincerely



Chris Bauld  
Group Manager - Tauranga

12-May-06  
j:\t&t hamilton jobs\60619\_lynley park\completion report\_stage1a\cjb120506.lot123\_completion.let.doc

"I hereby certify that the following works comply with the District Plan and Subdivision and Development Code of Practice:

Signed.....

Dated .....

**OR**

"As an independent professional I, or other personnel under my control, have carried out periodic reviews of the subdivision work appropriate as to the nature of the work. Based upon these reviews, on information supplied by independent professionals engaged in the work and by the contractor during the course of the subdivisional works [optional: and the contractor's certification upon completion of the subdivisional works - copy attached], I hereby certify on the basis of reasonable and appropriate enquiry, that the following subdivisional works

- ① Bulk earthworks as described in the Tonkin & Taylor Ltd report "Lynley Park Subdivision, Omokoroa - Stage 1a Geotechnical Completion Report" and dated February 2006.
- ② Bulk earthworks as described in the Tonkin & Taylor Ltd report "Lynley Park Subdivision, Omokoroa - Lot 123 Geotechnical Completion Report" and dated May 2006.
- ③ Pavement construction as described in the Tonkin & Taylor Ltd report "Lynley Park Subdivision, Omokoroa - Stage 1a Pavement Completion Report" and dated April 2006.


and subject to the limitations of these reports,

comply with the conditions of this consent and that the development work required by the conditions of consent has been undertaken in accordance with sound engineering design and construction practice and complies with the ~~District Plan and~~ Subdivision and Development Code of Practice."

Signed.....

Dated .....

12 May 2006



SECTION 224  
CERTIFICATION STATEMENT

WESTERN BAY OF PLENTY DISTRICT COUNCIL

1 - 1b

March  
2005

To: The Western Bay of Plenty District Council

**STATEMENT OF PROFESSIONAL OPINION AS TO THE  
GEOTECHNICAL SUITABILITY OF LAND FOR BUILDING**

DEVELOPMENT: Lynley Park Subdivision – Stage 1a  
OWNER: Durham Properties Ltd  
LOCATION: Omokoroa Road, Omokoroa Peninsula

I, Christopher John Bauld of Tonkin & Taylor Ltd, 12 Elizabeth Street, Tauranga, hereby confirm that:

- 1) I am a professional person, appropriately qualified with experience in geotechnical engineering to ascertain the suitability of the land for building development and was retained as the Soils Engineer for the above development.
- 2) An appropriate level of site investigation and construction supervision has been carried out under my direction and is described in the development evaluation report dated March 2004 (Stage 1, Lynley Park Omokoroa, Geotechnical Issues Report, Tonkin & Taylor Ltd).
- 3) In my professional opinion, not to be construed as a guarantee, I consider that:
  - a) The area shown in my letter dated 12 May 2006 of allotment 123 is suitable for the erection thereon of the building types appropriate to the zoning of the land, provided that: normal foundation inspections by the regulatory authorities and a suitably qualified engineer should be carried out during construction, and construction is in accordance with NZS 3604:1999 and related documents; building restriction lines indicate those areas where specific design is required.
  - b) The completed works give due regard to land slope and foundation stability considerations.
  - c) The earth fills shown on the attached plan (T&T Figure 3, rev 1), have been placed in accordance with the Subdivision and Development Code of Practice of the Western Bay of Plenty District Council.
  - d) The filled ground is suitable for the erection thereon of residential buildings not requiring specific design in terms of NZS 3604:1999 and related documents providing that
    - (i) normal foundation inspections by the regulatory authorities and a suitably qualified engineer should be carried out during construction
    - (ii) construction is inside of the designated building restriction lines.
    - (iii) The ground outside of the designated building restriction lines should be suitable for the erection thereon of residential buildings subject to specific engineering investigation and design.
    - (iv) Inspections are especially important where concrete blockwork and/or brick veneer or stucco plaster buildings are sited partly on fill or partly on natural ground, or where they are entirely sited on filling whose depth changes significantly across the building platform. Any variations in soil conditions from those described in our report, should be reported to Tonkin & Taylor Ltd
  - e) The original ground not affected by filling should be suitable for the erection thereon of residential buildings not requiring specific design in terms of NZS 3604:1999 and related documents provided that normal foundation inspections by the regulatory authorities and a suitably qualified engineer should be carried out during construction.
- 4) This professional opinion is furnished to the Council and the owner for their purpose alone, on the express condition that it will not be relied upon by any other person and does not remove the necessity for the normal inspection of foundation conditions at the time of erection for any dwelling.

Signed: \_\_\_\_\_



Date: \_\_\_\_\_

12 May 2006

**Lynley Park Residential Subdivision - Stage 1a, Omokoroa**  
**Summary of Geotechnical Data/Recommendations/Requirements for Individual Lots**

| Lot # | Area (m <sup>2</sup> ) | Subsurface Data                     |   | Foundations  |     |                     | Building line restriction?<br><br>Y/N | Recommendations/restrictions              |                      |         |
|-------|------------------------|-------------------------------------|---|--|-----|---------------------|---------------------------------------|---|----------------------|---------|
|       |                        | Subdivision filling<br>(TOTAL FILL) | Natural topography<br>earthworked?<br>(TOTAL CUT) | Conventional<br>shallow<br>foundation to<br>NZS<br>3604:1999 |     | Specific<br>design? |                                       |   |                      |         |
|       |                        |                                     |   | Average<br>Depth (m)   | Y/N |                     |                                       |   | Average<br>Depth (m) | Y/N/N/A |
|       |                        |                                     |   |  |     |                     |                                       |   |                      |         |
| 125   | 849                    | Y                                   | <0.5  | N  | N   | Y                   | N                                     | Foundation inspection during construction |                      |         |
| 126   | 821                    | Y                                   | <0.5  | N  | N   | Y                   | Y                                     | Foundation inspection during construction |                      |         |
| 127   | 849                    | N                                   | 1.5   | N  | N   | Y                   | N                                     | Foundation inspection during construction |                      |         |
| 128   | 880                    | N                                   | 1.5   | Y  | 0.5 | Y                   | N                                     | Foundation inspection during construction |                      |         |
| 129   | 864                    | N                                   | 1.5   | N  | 0.5 | Y                   | N                                     | Foundation inspection during construction |                      |         |
| 130   | 729                    | Y                                   | <0.5  | Y  | 1.5 | Y                   | N                                     | Foundation inspection during construction |                      |         |
| 131   | 745                    | Y                                   | <0.5  | N  | N   | Y                   | N                                     | Foundation inspection during construction |                      |         |
| 132   | 768                    | N                                   | 1.0   | N  | N   | Y                   | N                                     | Foundation inspection during construction |                      |         |
| 133   | 779                    | Y                                   | <0.5  | N  | N   | Y                   | N                                     | Foundation inspection during construction |                      |         |
| 134   | 870                    | Y                                   | 1.0   | N  | N   | Y                   | N                                     | Foundation inspection during construction |                      |         |
| 135   | 988                    | Y                                   | 1.5   | Y  | 0.5 | Y                   | N                                     | Foundation inspection during construction |                      |         |
| 136   | 822                    | Y                                   | <0.5  | Y  | 1.5 | Y                   | N                                     | Foundation inspection during construction |                      |         |
| 123   | 867                    | Y                                   | <0.5  | Y  | 2.0 | Y                   | N                                     | Foundation inspection during construction |                      |         |






Figure 3

T&T job no: 60619  
12 April 2006

Durham Property Investments Ltd  
PO Box 15197  
Dyonsdale  
Hamilton

Attention: Phillip Palmer

Dear Phillip

### **Lynley Park - Earthworks Completion Report**

#### **Introduction**

This letter provides responses to the Western Bay of Plenty District Council (WBOPDC) letter of 07 March 2006 that requests clarifications to the Tonkin & Taylor report *Durham Properties Ltd, Lynley Park Subdivision, Omokoroa, Stage 1a - Geotechnical Completion Report* dated February 2006.

The points are as referred to in the WBOPDC letter.

#### **4.3 - Maximum Cut Depth**

This section was extracted from the design report and the intent of it should be clarified.

The design intent of this was to overlay any sensitive soils **if they were encountered**. Construction observation did not reveal any sensitive soils at grade in these areas and hence the undercut and fill overlay was not carried out.

We do not consider that 900mm deep pile would be at risk in a 1.5m deep fill layer. Such piles are generally required for uplift loads. In the event that the critical load is downwards, a pile would need to be greater than 600mm in diameter for the 1B depth of influence to extend below the fill.

#### **4.6 Fill Induced Settlement**

The areas of significant fill depth mentioned in this section are not in the Stage 1a area.

Monitoring of the fill settlement has not been undertaken at this point. Please confirm if you wish this to be carried out for release of the Stage 1b certification.

## **Table 2 – Soil Testing Requirements**

Section 7.4.2.4 of NZS 4431:1989 states; *For many cohesive soils it is found that an acceptable minimum shear strength is 150 kPa and a maximum air voids is 10%. For particular soil types, and for reserve areas or road subgrades some variations from the above values may be appropriate.*

This standard allows for variation from the 150kPa stated as a typical acceptable value. We have specified a target shear strength for the fill materials that we consider is appropriate for the soils encountered on site. This shear strength is expected to provide fills that perform adequately and allow design of foundations in accordance with NZS 3604. In particular the high water content soils that are typical of the area mean that a high target shear strength may be difficult to achieve.

### **4 Suitability for Development**

We have not identified any areas where a restriction on piled foundations would be required.

### **5 Sensitive Soil**

The limitation on this lot is partially historical and is included on the original title for the lot. This was based on the fact that there was some potential for sub-horizontal, sensitive, soil layers in the ridge to daylight out of the natural slopes. Lot 12 was identified as one with potential for this.

Lots 9, 10 and 13 are entirely in areas of cut and were able to be inspected during construction. Lot 12 has areas at natural ground level and there was a slightly higher risk that sensitive soils might not be revealed on this lot if they exist. We also note that Lot 12 is relatively steep and will require more extensive cutting for building platforms, hence increasing the potential for construction difficulties if sensitive soils were encountered.

Because of the above factors it was considered prudent to continue the approach with this lot only. However, the risk is not considered high.

### **6 Appendix B – Plans**


The dotted areas on the plans indicate area not included in Stage 1a

### **7 Appendix C – Test Results**

Lot 30 was not retested as this was considered to be a minor variation with sufficient additional shear strength over the specification to ensure the fill still performed adequately. The pond bund (dam) testing is provided in the dam completion report.

Please do not hesitate to contact the undersigned if you have any further queries on this matter.

Yours sincerely

A handwritten signature in black ink, appearing to read 'Chris Bauld', with a stylized, cursive script.

Chris Bauld  
Group Manager - Tauranga

12-Apr-06  
f:\t&t hamilton jobs\60619\_lynley park\completion report\_stage1a\cjb120406.earthworksrep.let.doc



**AMENDED****RECEIVED**

09 MAY 2006

BY: \_\_\_\_\_

**LYNLEY PARK STAGE 1A****SCHEDULE OF COVENANTED AREAS**


| <b>Label</b> | <b>Lot Number</b> | <b>Purpose</b>       |
|--------------|-------------------|----------------------|
| B1/AK        | 1                 | Building Restriction |
| B2           | 2                 | Building Restriction |
| B3           | 3                 | Building Restriction |
| B4           | 4                 | Building Restriction |
| B5           | 5                 | Building Restriction |
| B6           | 6                 | Building Restriction |
| B7           | 7                 | Building Restriction |
| B8           | 83                | Building Restriction |
| B9           | 84                | Building Restriction |
| B10          | 78                | Building Restriction |
| B11          | 77                | Building Restriction |
| B12          | 76                | Building Restriction |
| B13          | 75                | Building Restriction |
| B14          | 74                | Building Restriction |
| B15/AM       | 73                | Building Restriction |
| B16          | 70                | Building Restriction |
| B17          | 69                | Building Restriction |
| B18          | 68                | Building Restriction |
| B19          | 67                | Building Restriction |
| B20          | 66                | Building Restriction |
| B21          | 65                | Building Restriction |
| B22          | 61                | Building Restriction |
| B23          | 60                | Building Restriction |
| B24          | 59                | Building Restriction |
| B25          | 58                | Building Restriction |
| B26          | 57                | Building Restriction |
| B27          | 54                | Building Restriction |
| B28          | 45                | Building Restriction |
| B29          | 44                | Building Restriction |
| B30          | 43                | Building Restriction |
| B31          | 42                | Building Restriction |

**AMENDED**

|   |
|---|
| <b>RECEIVED</b><br>09 MAY 2006<br>BY: _____ |
|---|

| Label  | Lot Number | Purpose   |
|--------|------------|---|
| B32    | 41         | Building Restriction  |
| B33    | 40         | Building Restriction  |
| B34    | 39         | Building Restriction  |
| B35    | 38         | Building Restriction  |
| B36    | 37         | Building Restriction  |
| B37    | 36         | Building Restriction  |
| B38    | 35         | Building Restriction  |
| B39    | 34         | Building Restriction  |
| B40    | 33         | Building Restriction  |
| B41    | 32         | Building Restriction  |
| B42/AL | 31         | Building Restriction  |
| B43    | 30         | Building Restriction  |
| B44    | 123        | Building Restriction  |
| C1     | 30         | Building Restriction,<br>Landscape (As per condition A2.2),<br>monitoring and maintenance of<br>buttress drains (condition A15.7) |
| C2/AH  | 31         | Building Restriction, Landscape<br>(As per condition A2.2),<br>monitoring and maintenance of<br>buttress drains (condition A15.7) |
| C3     | 32         | Building Restriction, Landscape<br>(As per condition A2.2)  |
| C4     | 33         | Building Restriction, Landscape<br>(As per condition A2.2)  |
| C5     | 34         | Building Restriction, Landscape<br>(As per condition A2.2),<br>monitoring and maintenance of<br>buttress drains (condition A15.7) |
| C6     | 35         | Building Restriction, Landscape<br>(As per condition A2.2),<br>monitoring and maintenance of<br>buttress drains (condition A15.7) |
| C7     | 36         | Building Restriction, Landscape<br>(As per condition A2.2)  |

**AMENDED**



| Label | Lot Number | Purpose   |
|-------|------------|---|
| C8    | 37         | Building Restriction, Landscape<br>(As per condition A2.2)  |
| C9    | 38         | Building Restriction, Landscape<br>(As per condition A2.2),<br>monitoring and maintenance of<br>buttress drains (condition A15.7) |
| C10   | 39         | Building Restriction, Landscape<br>(As per condition A2.2), monitoring<br>and maintenance of buttress drains<br>(condition A15.7) |
| C11   | 40         | Building Restriction, Landscape<br>(As per condition A2.2), monitoring<br>and maintenance of buttress drains<br>(condition A15.7) |
| C12   | 41         | Building Restriction, Landscape<br>(As per condition A2.2)  |
| C13   | 42         | Building Restriction, Landscape<br>(As per condition A2.2), monitoring<br>and maintenance of buttress drains<br>(condition A15.7) |
| C14   | 43         | Building Restriction, Landscape<br>(As per condition A2.2), monitoring<br>and maintenance of buttress drains<br>(condition A15.7) |
| C15   | 44         | Building Restriction, Landscape<br>(As per condition A2.2), monitoring<br>and maintenance of buttress drains<br>(condition A15.7) |
| C16   | 45         | Building Restriction, Landscape<br>(As per condition A2.2), monitoring<br>and maintenance of buttress drains<br>(condition A15.7) |
| C17   | 54         | Building Restriction, Landscape<br>(As per condition A2.2)  |

# **REPORT**

---

**DURHAM PROPERTIES LTD**

**Lynley Park Subdivision, Omokoroa  
Stage 1a - Geotechnical  
Completion Report**

---

**Report prepared for:**  
**DURHAM PROPERTIES LTD**

**Report prepared by:**  
**TONKIN & TAYLOR LTD**

**Distribution:**  
**DURHAM PROPERTIES LTD**  
**TONKIN & TAYLOR LTD (FILE)**

**5 copies**

**1 copy**

**February 2006**

**Job no: 60619**



## Table of contents

|             |                                   |    |
|-------------|-----------------------------------|----|
| 1.          | Introduction                      | 1  |
| 2.          | Available Site Data               | 1  |
| 3.          | Site Conditions                   | 2  |
| 3.1.        | Development Details               | 2  |
| 3.2.        | Site Description                  | 2  |
| 3.3.        | Geological Setting                | 2  |
| 4.          | Summary of Design Recommendations | 3  |
| 4.1.        | Introduction                      | 3  |
| 4.2.        | Slope Stability                   | 3  |
| 4.3.        | Maximum Cut Depth                 | 4  |
| 4.4.        | Fill Suitability                  | 4  |
| 4.5.        | Preparation of Fill Areas         | 5  |
| 4.6.        | Fill Induced Settlement           | 5  |
| 5.          | Construction                      | 5  |
| 6.          | Field Testing                     | 6  |
| 6.1.        | Inspections                       | 6  |
| 6.2.        | Fill Testing                      | 6  |
| 7.          | Suitability for Development       | 9  |
| 7.1.        | General Observations              | 9  |
| 7.2.        | Specific Issues                   | 9  |
| 7.2.1.      | Sensitive Soils                   | 9  |
| 7.2.2.      | Landscape Fill                    | 9  |
| 7.2.3.      | Reserve Walkway                   | 10 |
| 7.2.4.      | Building Restriction Lines        | 11 |
| 8.          | Applicability                     | 11 |
|             |                                   |    |
| Appendix A: | Certification                     |    |
| Appendix B: | Figures                           |    |
| Appendix C: | Field Density Tests               |    |
| Appendix D: | Earthworks Specification          |    |

## 1. Introduction

Tonkin & Taylor Ltd was engaged by Durham Properties Ltd to review Stage 1a earthworks for the Lynley Park subdivision at Omokoroa. Stage 1a of this subdivision includes development of 82 residential lots (being lots 1 to 70 inclusive and lots 73 to 84).

The work undertaken by Tonkin and Taylor comprised:

- An inspection of the site and the surrounding area by a senior geotechnical engineer prior to commencement of works;
- Design investigations, analysis and reporting;
- Regular site visits by geotechnical engineering staff to observe the cut-to-fill earthworks. Field density testing of the compacted fill was carried out by the contractor using a nuclear densometer along with shear vane testing of soils for strength;

The above work has been carried out to support the attached "Statement of Professional Opinion as to the Suitability of Land for Building Development" (Appendix A).

This engagement was specific to earthworks and geotechnical matter only on this development. Overall completion reporting for the development is reported elsewhere by CKL Ltd. This report does not include certification of retaining walls on the site. This is to be provided by others.

## 2. Available Site Data

Several geotechnical reports have been prepared for the subdivision area. These have included factual reporting of geotechnical investigation data and design recommendations. The applicable reports are as follows;

### Reference Report 1

*"Geotechnical Investigation Report on Lynley Park residential subdivision at Omokoroa Road, Omokoroa Peninsula"*, report prepared by Foundation Engineering Ltd for Durham Property Investments Ltd, dated the 16<sup>th</sup> of December 1999, project number 8425.

### Reference Report 2

*"Supplementary Geotechnical Investigation Report on Lynley Park residential subdivision Stage 1 at Omokoroa Road, Omokoroa"*, report prepared by Foundation Engineering Ltd for Durham Property Investments Ltd, dated the 15<sup>th</sup> of April 2002, project number 8425.

### Reference Report 3

*"Durham Investment Properties Ltd - Stage 1, Lynley Park Omokoroa Geotechnical Issues Report"*, prepared by Tonkin & Taylor Ltd and dated March 2004.



## Reference Report 4

*"Durham Investment Properties Ltd -Lynley Park Subdivision Omokoroa, Tauranga Geotechnical Geotechnical Investigations for Northern Boundary", prepared by Tonkin & Taylor Ltd and dated January 2004.*

This report must be read in conjunction with the data included in these reports. We note that design concepts for the works have changed since preparation of the reports by Foundation Engineering. Because of this the Foundation Engineering reports may be considered to be a source of factual data only.

Design details of the overall development are included in completion reporting by CKL Ltd.

## 3. Site Conditions

### 3.1. Development Details

Stage 1a is accessed along Omokoroa Road with the general layout of this stage being shown on the drawing T&T Ref. Figure 1, Figure 2 and Figure 3, in Appendix B. This is the first separable portion of the works.

Design details of the overall development are included in completion reporting by CKL Ltd.

### 3.2. Site Description

The original site topography was dominated by a north-east to south-west trending ridge and gully which run parallel to each other towards the coastal flank of the site. The top of the ridge has a predominantly gentle rolling slope towards the north-east of the block, however the sidling slopes grade sharply down a moderate to steep (25 to 40°) slope to the north-east and south-east of the ridge and down less inclined, moderately steep (15 to 20°) slope to the north-west to Omokoroa Road below.

To the south of the ridge system is an incised, scrub clad gully that provides a drainage path for run-off within the area to the estuarine harbour and a section of undulating terrain which is encompassed in Stage II of the proposed development. There are several geotechnical issues that surround the development of these two features, however they are not within the area covered by this report and will be addressed separately.

The East Coast Main Trunk railway crosses beneath Omokoroa Road and traverses the south-western boundary of the site. This section of the railway has been formed within a near vertical, unsupported box cut at approximately 10m below the existing site ground level.

Much the current geomorphology of the site, particularly on the north-eastern and south-eastern flanks of the ridge, can be attributed to landslipping, the mechanism of which will be discussed in the following sections.

### 3.3. Geological Setting

The geological strata forming the Omokoroa Peninsula and underlying the majority of the site can be broadly divided into three main units that overlie the ignimbrite



basement, which is inferred to underlie the basin into which these units were deposited.

The older of the three units is known as the Matua Subgroup, an assemblage of terrestrial and estuarine sediments and interbedded ashes that formed within an ancient river/estuary system. Sedimentary deposits comprise well sorted gravel and sand deposits, carbonaceous silts and muds together with peat horizons. Many of these deposits are inter-fingered with volcanic breccias and ashes derived from Rotorua - Taupo volcanism.

Directly-overlying these is the deeply-weathered clay-rich Hamilton Ash, which blankets much of the Waikato and northern Bay of Plenty Region.

The Rotoehu Ash and other young less weathered ashes constitute the youngest unit. These comprise a sequence of young rhyolitic air fall ashes between 2 and 4m thick that covers much of the Omokoroa Peninsula.

This data was based on information available from published geological maps of the area (IGNS 1:50,000 series) and the Tonkin & Taylor geotechnical database.

Construction works on site have confirmed this inferred geology.

A detailed description of the geological model, engineering design and recommendations is included in Reference Report 3.

## **4. Summary of Design Recommendations**

### **4.1. Introduction**

This section is intended to provide the design recommendations contained in Reference Report 3. Any detailed assessment will require reference to that report.

### **4.2. Slope Stability**

As highlighted in previous sections of this report there was geomorphic evidence of past instability within the site, in particular within the south-eastern sidling slope and the north-eastern point of the main ridge. Analysis indicates that ridge slopes originally existed with a factor of safety between 1.5 and 2.5 which is considered 'stable' for slopes under long term static conditions. Analysis also shows that earthworks should generally improve the long term FOS under drained slope conditions. However, a reduction in the FOS for slopes results from pore water pressure increases within the underlying Pahoia Tephra layer when modelling both existing and post-earthwork conditions.

A Building Restriction Line (BRL) was identified during design for the proposed lots adjacent to the south-eastern sidling slope and the north-eastern point, the areas which are of most concern. The BRL is a setback from existing slip scarps and from the inferred regression line of the intact spurs between arcuate slip features. This line has been modified following construction to fit better with actual conditions on site. The final location of the BRL is shown on the figures in Appendix B

In order to minimise the affects of instability or the potential for it to occur the pore water pressures within the Pahoia Ash will need to be controlled and minimised to reduce the risk of instability. This has been undertaken by buttress drains cut into the subsoil in the upper part of the slope and back-filled with free draining

aggregate to control pore water pressure within the Ash. Final locations of the buttress drains have been assessed based on selecting areas of obvious high regression rates. As built locations of the buttress drains are included on the figures in Appendix B.

A further building restriction lines have been defined along the boundary with the existing railway cutting and along the Omokoroa Road frontage slope to ensure that building platforms are located away from these slopes. The lines are also shown on the figures in Appendix B

### 4.3. Maximum Cut Depth

The subsurface profile established for the site indicated that the main ridge area is mantled by between 3 to 6m of unweathered to slightly weathered sandy and silty ash overlying up to 5m thick silt (Pahoia Ash). Laboratory results and field observations showed that the Pahoia Ash is highly sensitive to disturbance and has a high water content well in excess of optimum and close to or above its liquid limit. In considering these two properties of the Pahoia Ash it was considered unlikely that this material could be practically utilised for engineered fill since handling the material will encounter great difficulties due to drying times and traffickability of cut surfaces.

The overlying ash units have lower moisture contents and lower sensitivity and would be, subject to conditioning, ideal for the use as engineered fill. However to satisfy the site requirements for NZS3604:1999 *Timber Framed Structures* we recommended that a minimum of 1.5m of the upper Ash material remain over the underlying highly sensitive Ash. Final cut levels were based on this recommendation.

The north-western ridge, which extends from the south-western end of the main ridge towards Omokoroa Road, was lowered up to 7.0m to establish the main access road into the area. Sections within this area have also been recontoured to slope northwards. To achieve this, localised cuts have extended into the underlying sensitive soils. For localised cuts extending below the stiff ash profile, undercutting of the underlying softer soil was undertaken and desired ground levels established with a minimum of 1.5m of engineered fill

### 4.4. Fill Suitability

The earthworks operation involved up to 4.5m of cut from the main ridge on site and subsequent filling of the northern low lying area. Other cut and fill operations involved the lowering of the north-western ridge to provide an accessway to the development. The soils encountered were generally expected to comprise clayey silts, sandy silts and pumiceous silty sands. These materials should, with appropriate conditioning, be suitable for handling and compaction by conventional earthmoving plant.

Where localised undercutting of soft ground has taken place the cut material often had high moisture contents and was either spread to be dried (if to be used for fill) or cut to waste.



An earthworks specification was prepared for the cut and fill operation undertaken on-site. This is included in Appendix D.

#### **4.5. Preparation of Fill Areas**

Subsurface investigations undertaken within the proposed fill areas indicated the presence of either soft compressible soil or colluvial debris derived from landslippage in the area. The fill subgrade was inspected and approved by the Engineer following the stripping of topsoil from the fill area and prior to placement of fill. Any identified unsuitable material was undercut and disposed of to an approved disposal area.

Earthworks was carried out in accordance with NZS 4404:1981 *Code of practice for Urban Land Subdivision*, including benching of slopes prior to the placement and compaction of fill. This should ensure that the fill is keyed into the underlying natural ground.

#### **4.6. Fill Induced Settlement**

The majority of the fill has taken place in the main depression that runs between the main ridge and Omokoroa Road, in which between 2 to 4m of engineered fill was placed. Due to the presence of soft and compressible natural soil which underlies this area it is expected that there will be some fill induced settlement. The majority of the settlement is expected to occur during fill placement and settlements within building platforms are expected to be minimal.

### **5. Construction**

The earthworks were carried out by A&R Earthmovers Ltd in 2004 to 2006, with final cut-fill contours shown on the attached plan T&T Ref. Figure 1, 2 & 3. The cut-fill contours show the maximum depth of cut or fill from final ground contours. The earthworks included the following:

- i. Topsoil stripping and removal of unsuitable organic material from existing ground and surplus quantities removed off site.
- ii. Cutting high ridge areas to reduce ground height and provide fill materials. This included undercutting in areas where filling was required over sensitive soils.
- iii. Placement of on site fill to contours as shown on the final fill plan.
- iv. Road excavation and services installation.
- v. Construction of retaining walls adjacent to Road 1.
- vi. Placement of Landscape fill on Lots 30-45 and Lot 54 to form buttressing, catch benches and access tracks.
- vii. Construction of buttress drains
- viii. Topsoil replaced over the proposed lots to a maximum depth of 300mm.

Fill was placed in accordance with the project earthworks specification, which complies with the Western Bay of Plenty District Council (WBoPDC) requirements for subdivisional earthworks. Compaction of the fill in open areas was carried out by trafficking of a fully laden scraper in a systematic manner over the fill areas or



using a sheeps foot roller where further compactive effort was required to meet the specification.

Tests were carried out by the Contractor as the earthworks progressed and on completion of the earthworks, indicating various passing and failing tests as summarised in Appendix C. The fill was removed in the areas found to be failing, replaced in layers, conditioned and recompacted. All failing areas were subsequently retested.

The as-built drawings attached in Figure 1, 2 & 3, Appendix B, show the extent of cut and fill for the earthworks. A maximum cut depth of 6.0m is shown in Lots 2 & 3. The areas of maximum fill, up to 4.0m depth, were located in Lot 26.

A producer statement construction (PS3) has been supplied by the Contractor and is included in Appendix A.

Construction observation did not include observation of the retaining walls constructed on site.

## **6. Field Testing**

### **6.1. Inspections**

Regular engineering inspections were carried out during the earthworks to confirm that organic and unsuitable material were identified and removed before filling commenced.

### **6.2. Fill Testing**

Fill control was undertaken using shear strength and maximum air voids ratios to confirm adequacy of compaction. The following criteria are taken from the earthworks specification that is included in Appendix D.

**TABLE 1 : Compaction Testing**

| Test  | Method   | Notes  |
|---|--|--|
| Vane Shear  | NZ Geotechnical Society Guidelines for Hand-held Shear Vane (2002) | The result shall be taken as the mean of at least 4 No. readings within a area of $\geq 0.5\text{m}^2$ , located within representative zones of the material being tested. |
| Water Content   | NZS4402  |  |
| Dry Density   | NZS4402  |  |
| Air Voids   | NZS4402  |  |
| Solid Density   | NZS4402  | 1 test per material type, subject to Geotechnical Engineer's written approval, and provided the nature of the fill remains consistent.                                     |
| Notes:<br>Additional tests should be carried out if the nature of the fill changes, or at the direction of the Engineer.<br>Tests shall be accordance with NZS4402 <i>Methods of Testing Soils for Civil Engineering Purposes</i> , as appropriate. |  |  |



**TABLE 2 : Fill Testing Requirements**

| Fill Type   | Test                     | Min. frequency   | Criteria   |
|---|--------------------------|--|--|
| Structural Fill more than 1.0 m below finished level  | Water Content            | 1 per 2,000 m <sup>3</sup>   | Minimum = 35 %<br>Maximum = 60 %                                   |
|   | Air Voids                | 1 per 2,000 m <sup>3</sup>   | Maximum = 10.0 %   |
|   | Undrained Shear Strength | 1 per 500 m <sup>3</sup> ,<br>reducible to 1 per 1000 m <sup>3</sup>                         | Average result $\geq 115$ kPa<br>Any single reading $\geq 110$ kPa |
| Structural Fill less than 1.0 m below finished level  | Water Content            | 1 per 2,000 m <sup>3</sup>   | Minimum = 35 %<br>Maximum = 60 %                                   |
|   | Air Voids                | 1 per 1,000 m <sup>3</sup><br>1 per 1,000 m <sup>2</sup> for filling less than <500 mm thick | Maximum = 8.0 %  |
|   | Undrained Shear Strength | 1 per 500 m <sup>3</sup>   | Average result $\geq 125$ kPa<br>Any single reading $\geq 115$ kPa |
| Non-structural Fill   | Air Voids                | 1 per 3,000 m <sup>3</sup><br>provided <1000 mm lifts  | Maximum = 14 %   |
|   | Undrained Shear Strength | 1 per 1,000 m <sup>3</sup> ,<br>reducible to 1 per 2000 m <sup>3</sup>                       | Average result $\geq 60$ kPa<br>Any single reading $\geq 60$ kPa   |
| <p>Notes:</p> <p>The frequency of testing will depend on the consistency of fill operations and materials used, and may be varied by the Engineer to obtain sufficient spatial coverage through the depth and extent of the filling.</p> <p>Additional tests should be carried out if the nature of the fill changes, or at the direction of the Engineer.</p> <p>The Engineer and Contractor shall continue to monitor earthworks operations. Once materials are consistent and work is being carried out in a systematic and consistent manner, the Engineer may vary the frequency of testing.</p> |                          |  |  |

Earthworks testing results are included in Appendix C.



## **7. Suitability for Development**

### **7.1. General Observations**

Based on our site observations, the method of fill placement, and the results of compaction control tests carried out during earthworks, we are of the opinion that the developed lots (being Lots 1 to 70 and lots 73 - 84) of Stage 1a of the Lynley Park Subdivision, are generally suitable for residential development in accordance with NZS 3604:1999 "Timber Framed Buildings". Some specific locations will require additional consideration and are described in Section 7.2.

All foundations should be founded in competent fill and/or natural ground below the topsoil layer. Settlement of buildings constructed in accordance with NZS 3604:1999 is expected to be less than 20 mm. Due to the presence of sensitive soils on the site it is necessary for foundations to be inspected by a suitably qualified professional to ensure that there are no specific hazards at the foundation locations. If sensitive soils are encountered then some alterations will be required to foundation construction. These should be undertaken by a suitably qualified professional.

For buildings which do not meet the requirements of NZS 3604:1999, we recommend a site specific investigation and design by a suitably qualified professional.

This opinion does not remove the requirement for foundation inspection as would normally be carried out during construction by the relevant regulatory authorities. Any local soft spots identified shall be excavated and replaced with compacted hardfill. If actual conditions encountered are different from those described in this report, we should be notified.

### **7.2. Specific Issues**

#### **7.2.1. Sensitive Soils**

A projection of soil layers indicates that there is some risk that sensitive soils encountered on site may be found at the surface along the north eastern face of the main ridge. This may effect Lot 12 in Stage 1a of the development.

Because of this, and the sloping ground, we consider that any development of these sites should be reviewed by a geotechnical professional. This may include investigations, design or design review along with observation of soils during construction to confirm soil conditions.

#### **7.2.2. Landscape Fill**

##### **7.2.2.1. Description of Fill**

Landscape fill has been placed along the south eastern face of the main ridge. This generally covers the lower sloping areas of Lots 30 - 45 and Lot 54, along with the Reserve vested below these properties. This fill has been placed to achieve three purposes;

- To form a track along the reserve area
- To provide buttressing to lower areas of the main slopes



- To provide a debris catch bench below the upper slopes of the ridge.

This fill was compacted by track rolling and consists of a mixture of higher water content ash soils and organic rich surface soils. Control testing was not undertaken for this filling.

The fill on the reserve land has been constructed to form a 3m wide track shown on the sub-division design drawings. The maximum slope for this fill is 3 horizontal to 1 vertical and is flatter than this in many areas. Additional fill was also placed in upper areas of the slopes above the walkway to provide shaping of the natural contours. The slope of this fill is steeper than 3:1 in areas.

None of the fill has been placed within building platform areas on Stage 1a for the subdivision. Fill is either included within the reserve area or outside building restriction lines on building Lots.

#### **7.2.2.2. Engineering Assessment**

Landscape fill has not been engineered and would not be expected to meet normal engineering criteria for stability or foundation construction. However, the specific application of this fill is within areas isolated from building platforms.

There is expected to be a moderate risk of shallow slumping in the fill above the track where the slopes are relatively steep. This would be likely to happen in periods of high rainfall. We would expect that debris from this slumping would be mostly trapped by the formed track and would not present a significant risk lower on the slope.

We expect that the relatively flat slopes of the landscape fill below the track location will mean the risk of significant failure is low. Any slumping would be expected to be surficial with little or no run-out.

This fill is not expected to provide additional risk to building platforms identified for lots. However, consideration should be taken of this fill when constructing any structures across the BRL.

#### **7.2.3. Reserve Walkway**

The reserve walkway has been constructed from formed Landscape filling as described above. This walkway is not considered to be a structure in terms of the Building Act. However, some consideration is required to ensure that the track retains utility and does not require excessive maintenance.

Two hazards may be considered for the walkway. Slumping of the fill forming the track may occur and require re-shaping of the track. In addition there is the risk of debris slumping from slopes above the track that would require clearance.

Slumping of the fill below the track is expected to be a relatively low risk as fill slopes are shallow. In addition there are surface water collection systems installed on the track to ensure that ponding of water does not result in saturation of the slope.

Slumping from above the track is considered a moderate risk that would be unacceptable for a building structure. However, we expect that slumping will be relatively rare (ie several years between incidents) and generally of relatively low volume.

We consider that the stability issues associated with the track are consistent with those that may be expected from a non-engineered access in a reserve.

#### **7.2.4. Building Restriction Lines**

Proposed buildings that extend beyond the specified building restriction lines will need to address the instability issue with suitably engineered retention and drainage. We expect that these issues will generally be feasible to address but may require careful consideration to confirm that the proposed works are economic.

A building restriction line has also been defined by others to ensure construction remains clear of retaining walls on site. Any structures located within this line are to be subject to specific design to ensure additional load is not placed on these retaining walls. These lines are also shown on the figures in Appendix B.

### **8. Applicability**

This report has been prepared solely for the benefit of Durham Properties Ltd with respect to the particular brief given to us, and it may not be released to third parties, other than Western Bay of Plenty District Council, for any purpose without our prior review and written agreement.

TONKIN & TAYLOR LTD  
Environmental and Engineering Consultants

Report prepared by:



C. J. Bauld  
Senior Geotechnical Engineer  
Office Manager - Tauranga

smbj  
J:\T&T Hamilton jobs\60619\_Lynley Park\Completion Report\_Stage1a\ST1a.smbj.221105.report.doc



---

## **Appendix A:     Certification**

To: The Western Bay of Plenty District Council

**STATEMENT OF PROFESSIONAL OPINION AS TO THE  
GEOTECHNICAL SUITABILITY OF LAND FOR BUILDING**

DEVELOPMENT: Lynley Park Subdivision – Stage 1a  
OWNER: Durham Properties Ltd  
LOCATION: Omokoroa Road, Omokoroa Peninsula

I, Christopher John Bauld of Tonkin & Taylor Ltd, 12 Elizabeth Street, Tauranga, hereby confirm that:

- 1) I am a professional person, appropriately qualified with experience in geotechnical engineering to ascertain the suitability of the land for building development and was retained as the Soils Engineer for the above development.
- 2) An appropriate level of site investigation and construction supervision has been carried out under my direction and is described in the development evaluation report dated March 2004 (Stage 1, Lynley Park Omokoroa, Geotechnical Issues Report, Tonkin & Taylor Ltd).
- 3) In my professional opinion, not to be construed as a guarantee, I consider that:
  - a) The areas shown in my report dated February 2006 of each new allotment or on the development site are suitable for the erection thereon of the building types appropriate to the zoning of the land, provided that: normal foundation inspections by the regulatory authorities and a suitably qualified engineer should be carried out during construction, and construction is in accordance with NZS 3604:1999 and related documents; building restriction lines indicate those areas where specific design is required.
  - b) The completed works give due regard to land slope and foundation stability considerations.
  - c) The earth fills shown on the attached plan (T&T Figures 1, 2 & 3), have been placed in accordance with the Subdivision and Development Code of Practice of the Western Bay of Plenty District Council.
  - d) The filled ground is suitable for the erection thereon of residential buildings not requiring specific design in terms of NZS 3604:1999 and related documents providing that
    - (i) normal foundation inspections by the regulatory authorities and a suitably qualified engineer should be carried out during construction
    - (ii) construction is inside of the designated building restriction lines.
    - (iii) The ground outside of the designated building restriction lines should be suitable for the erection thereon of residential buildings subject to specific engineering investigation and design.
    - (iv) Inspections are especially important where concrete blockwork and/or brick veneer or stucco plaster buildings are sited partly on fill or partly on natural ground, or where they are entirely sited on filling whose depth changes significantly across the building platform. Any variations in soil conditions from those described in our report, should be reported to Tonkin & Taylor Ltd
  - e) The original ground not affected by filling should be suitable for the erection thereon of residential buildings not requiring specific design in terms of NZS 3604:1999 and related documents provided that normal foundation inspections by the regulatory authorities and a suitably qualified engineer should be carried out during construction.
- 4) This professional opinion is furnished to the Council and the owner for their purpose alone, on the express condition that it will not be relied upon by any other person and does not remove the necessity for the normal inspection of foundation conditions at the time of erection for any dwelling.

Signed: \_\_\_\_\_



Date: \_\_\_\_\_

22/02/06

**Lynley Park Residential Subdivision - Stage 1a, Omokoroa**  
**Summary of Geotechnical Data/Recommendations/Requirements for Individual Lots**

| Lot # | Area (m <sup>2</sup> ) | Subsurface Data                     |                      |   |       | Foundations  |                     |       | Building line restriction?<br><br>Y/N | Recommendations/restrictions              |
|-------|------------------------|-------------------------------------|----------------------|---|-------|--|---------------------|-------|---------------------------------------|---|
|       |                        | Subdivision filling<br>(TOTAL FILL) |                      | Natural topography<br>earthworked?<br>(TOTAL CUT) |       | Conventional<br>shallow<br>foundation to<br>NZS<br>3604:1999 | Specific<br>design? | Y/N/A |                                       |   |
|       |                        |                                     |                      |   |       |  |                     |       |                                       |   |
|       |                        | Y/N                                 | Average<br>Depth (m) | Y/N/A   | Y/N/A |  |                     |       |                                       |   |
| 1     | 800                    | N                                   | -                    | Y   | 4.5   | Y  | N                   | N     | Y                                     | Foundation inspection during construction |
| 2     | 751                    | N                                   | -                    | Y   | 6.0   | Y  | N                   | N     | Y                                     | Foundation inspection during construction |
| 3     | 773                    | N                                   | -                    | Y   | 6.0   | Y  | N                   | N     | Y                                     | Foundation inspection during construction |
| 4     | 721                    | N                                   | -                    | Y   | 5.5   | Y  | N                   | N     | Y                                     | Foundation inspection during construction |
| 5     | 703                    | N                                   | -                    | Y   | 2.5   | Y  | N                   | N     | Y                                     | Foundation inspection during construction |
| 6     | 737                    | N                                   | -                    | Y   | 1.5   | Y  | N                   | N     | Y                                     | Foundation inspection during construction |
| 7     | 869                    | Y                                   | <0.5                 | Y   | 0.5   | Y  | N                   | N     | Y                                     | Foundation inspection during construction |
| 8     | 626                    | Y                                   | <0.5                 | Y   | 1.5   | Y  | N                   | N     | N                                     | Foundation inspection during construction |
| 9     | 746                    | Y                                   | <0.5                 | Y   | 2.0   | Y  | N                   | N     | N                                     | Foundation inspection during construction |
| 10    | 884                    | N                                   | -                    | Y   | 3.0   | Y  | N                   | N     | N                                     | Foundation inspection during construction |
| 11    | 1351                   | N                                   | -                    | Y   | 4.0   | Y  | N                   | N     | N                                     | Foundation inspection during construction |
| 12    | 1886                   | Y                                   | 0.5                  | Y   | 2.5   | N  | Y                   | Y     | N                                     | Specific design required                  |
| 13    | 699                    | N                                   | -                    | Y   | 2.0   | Y  | N                   | N     | N                                     | Foundation inspection during construction |
| 14    | 699                    | N                                   | -                    | Y   | 3.5   | Y  | N                   | N     | N                                     | Foundation inspection during construction |

**Lynley Park Residential Subdivision - Stage 1a, Omokoroa**  
**Summary of Geotechnical Data/Recommendations/Requirements for Individual Lots**

| # Lot | Area (m <sup>2</sup> ) | Subsurface Data                     |                      |   |                      | Foundations  |                     |        | Building line restriction?<br><br>Y/N     | Recommendations/restrictions |
|-------|------------------------|-------------------------------------|----------------------|---|----------------------|--|---------------------|--------|---|------------------------------|
|       |                        | Subdivision filling<br>(TOTAL FILL) |                      | Natural topography<br>earthworked?<br>(TOTAL CUT) |                      | Conventional<br>shallow<br>foundation to<br>NZS<br>3604:1999 | Specific<br>design? |        |   |                              |
|       |                        | Y/N                                 | Average<br>Depth (m) | Y/N   | Average<br>Depth (m) |  |                     |        |   |                              |
|       |                        |                                     |                      |   |                      |  |                     | Y/N/NA |   |                              |
| 15    | 759                    | N                                   | -                    | Y   | 4.5                  | Y  | N                   | N      | Foundation inspection during construction |                              |
| 16    | 734                    | N                                   | -                    | Y   | 3.5                  | Y  | N                   | N      | Foundation inspection during construction |                              |
| 17    | 753                    | N                                   | -                    | Y   | 3.5                  | Y  | N                   | N      | Foundation inspection during construction |                              |
| 18    | 783                    | Y                                   | 2.0                  | Y   | 2.0                  | Y  | N                   | N      | Foundation inspection during construction |                              |
| 19    | 743                    | Y                                   | 0.5                  | Y   | 2.5                  | Y  | N                   | N      | Foundation inspection during construction |                              |
| 20    | 1266                   | Y                                   | <0.5                 | Y   | 3.0                  | Y  | N                   | N      | Foundation inspection during construction |                              |
| 21    | 804                    | N                                   | -                    | Y   | 3.5                  | Y  | N                   | N      | Foundation inspection during construction |                              |
| 22    | 821                    | N                                   | -                    | Y   | 3.0                  | Y  | N                   | N      | Foundation inspection during construction |                              |
| 23    | 842                    | Y                                   | <0.5                 | Y   | 3.0                  | Y  | N                   | N      | Foundation inspection during construction |                              |
| 24    | 1464                   | Y                                   | <0.5                 | Y   | 2.5                  | Y  | N                   | N      | Foundation inspection during construction |                              |
| 25    | 891                    | N                                   | -                    | Y   | 2.5                  | Y  | N                   | N      | Foundation inspection during construction |                              |
| 26    | 2274                   | Y                                   | 4.0                  | Y   | 2.0                  | Y  | N                   | N      | Foundation inspection during construction |                              |
| 27    | 2123                   | Y                                   | 3.0                  | Y   | 3.0                  | Y  | N                   | N      | Foundation inspection during construction |                              |
| 28    | 1376                   | Y                                   | 1.5                  | Y   | 3.0                  | Y  | N                   | N      | Foundation inspection during construction |                              |



**Lynley Park Residential Subdivision - Stage 1a, Omokoroa**  
**Summary of Geotechnical Data/Recommendations/Requirements for Individual Lots**

| Lot # | Area (m <sup>2</sup> ) | Subsurface Data                     |                      |   |                      | Foundations  |                     |   | Building line restriction?<br><br>Y/N     | Recommendations/restrictions |
|-------|------------------------|-------------------------------------|----------------------|---|----------------------|--|---------------------|---|---|------------------------------|
|       |                        | Subdivision filling<br>(TOTAL FILL) |                      | Natural topography<br>earthworked?<br>(TOTAL CUT) |                      | Conventional<br>shallow<br>foundation to<br>NZS<br>3604:1999 | Specific<br>design? |   |   |                              |
|       |                        |                                     |                      |   |                      |  |                     |   |   |                              |
|       |                        | Y/N                                 | Average<br>Depth (m) | Y/N   | Average<br>Depth (m) | Y/N/NA   | Y/N/NA              |   |   |                              |
| 29    | 952                    | Y                                   | <0.5-                | Y   | 2.5                  | Y  | N                   | N | Foundation inspection during construction |                              |
| 30    | 3373                   | N                                   | -                    | Y   | 2.5                  | Y  | N                   | Y | Foundation inspection during construction |                              |
| 31    | 2404                   | Y                                   | 0.5                  | Y   | 3.0                  | Y  | N                   | Y | Foundation inspection during construction |                              |
| 32    | 1631                   | Y                                   | 1.5                  | Y   | 3.0                  | Y  | N                   | Y | Foundation inspection during construction |                              |
| 33    | 1931                   | Y                                   | 1.5                  | Y   | 3.0                  | Y  | N                   | Y | Foundation inspection during construction |                              |
| 34    | 1746                   | Y                                   | 1.0                  | Y   | 3.5                  | Y  | N                   | Y | Foundation inspection during construction |                              |
| 35    | 1659                   | Y                                   | 1.5                  | Y   | 3.5                  | Y  | N                   | Y | Foundation inspection during construction |                              |
| 36    | 1882                   | Y                                   | 0.5                  | Y   | 3.5                  | Y  | N                   | Y | Foundation inspection during construction |                              |
| 37    | 1794                   | Y                                   | 0.5                  | Y   | 3.5                  | Y  | N                   | Y | Foundation inspection during construction |                              |
| 38    | 1462                   | Y                                   | 0.5                  | Y   | 3.5                  | Y  | N                   | Y | Foundation inspection during construction |                              |
| 39    | 1490                   | Y                                   | 1.5                  | Y   | 4.0                  | Y  | N                   | Y | Foundation inspection during construction |                              |
| 40    | 1612                   | Y                                   | 0.5                  | Y   | 4.0                  | Y  | N                   | Y | Foundation inspection during construction |                              |
| 41    | 1697                   | Y                                   | 1.0                  | Y   | 4.5                  | Y  | N                   | Y | Foundation inspection during construction |                              |
| 42    | 1507                   | Y                                   | 1.5                  | Y   | 4.5                  | Y  | N                   | Y | Foundation inspection during construction |                              |

**Lynley Park Residential Subdivision - Stage 1a, Omokoroa**  
**Summary of Geotechnical Data/Recommendations/Requirements for Individual Lots**

| Lot # | Area (m <sup>2</sup> ) | Subsurface Data                     |                      |   |                      | Foundations  |                     |   | Building line restriction?<br><br>Y/N | Recommendations/restrictions              |
|-------|------------------------|-------------------------------------|----------------------|---|----------------------|--|---------------------|---|---------------------------------------|---|
|       |                        | Subdivision filling<br>(TOTAL FILL) |                      | Natural topography<br>earthworked?<br>(TOTAL CUT) |                      | Conventional<br>shallow<br>foundation to<br>NZS<br>3604:1999 | Specific<br>design? |   |                                       |   |
|       |                        |                                     |                      |   |                      |  |                     |   |                                       |   |
|       |                        | Y/N                                 | Average<br>Depth (m) | Y/N   | Average<br>Depth (m) | Y/N/NA   | Y/N/NA              |   |                                       |   |
| 43    | 1575                   | Y                                   | 2.0                  | Y   | 4.5                  | Y  | N                   | N | Y                                     | Foundation inspection during construction |
| 44    | 1486                   | Y                                   | 1.5                  | Y   | 4.0                  | Y  | N                   | N | Y                                     | Foundation inspection during construction |
| 45    | 1495                   | Y                                   | 2.5                  | Y   | 3.0                  | Y  | N                   | N | Y                                     | Foundation inspection during construction |
| 46    | 753                    | N                                   | -                    | Y   | 1.5                  | Y  | N                   | N | N                                     | Foundation inspection during construction |
| 47    | 837                    | N                                   | -                    | Y   | 1.0                  | Y  | N                   | N | N                                     | Foundation inspection during construction |
| 48    | 883                    | Y                                   | 1.0                  | Y   | 1.5                  | Y  | N                   | N | N                                     | Foundation inspection during construction |
| 49    | 1073                   | Y                                   | 2.0                  | Y   | 1.5                  | Y  | N                   | N | N                                     | Foundation inspection during construction |
| 50    | 882                    | Y                                   | 3.0                  | N   | -                    | Y  | N                   | N | N                                     | Foundation inspection during construction |
| 51    | 797                    | Y                                   | 3.0                  | N   | -                    | Y  | N                   | N | N                                     | Foundation inspection during construction |
| 52    | 937                    | Y                                   | 1.5                  | N   | -                    | Y  | N                   | N | N                                     | Foundation inspection during construction |
| 53    | 896                    | Y                                   | 1.0                  | Y   | 0.5                  | Y  | N                   | N | N                                     | Foundation inspection during construction |
| 54    | 1975                   | Y                                   | 2.0                  | Y   | 2.0                  | Y  | N                   | N | Y                                     | Foundation inspection during construction |
| 55    | 1073                   | Y                                   | <0.5                 | Y   | 1.0                  | Y  | N                   | N | N                                     | Foundation inspection during construction |
| 56    | 719                    | N                                   | -                    | Y   | 2.0                  | Y  | N                   | N | N                                     | Foundation inspection during construction |

**Lynley Park Residential Subdivision - Stage 1a, Omokoroa**  
**Summary of Geotechnical Data/Recommendations/Requirements for Individual Lots**

| Lot # | Area (m <sup>2</sup> ) | Subsurface Data                     |                      |   |                      | Foundations  |                     |   | Building line restriction?<br><br>Y/N     | Recommendations/restrictions |
|-------|------------------------|-------------------------------------|----------------------|---|----------------------|--|---------------------|---|---|------------------------------|
|       |                        | Subdivision filling<br>(TOTAL FILL) |                      | Natural topography<br>earthworked?<br>(TOTAL CUT) |                      | Conventional<br>shallow<br>foundation to<br>NZS<br>3604:1999 | Specific<br>design? |   |   |                              |
|       |                        |                                     |                      |   |                      |  |                     |   |   |                              |
|       |                        | Y/N                                 | Average<br>Depth (m) | Y/N   | Average<br>Depth (m) | Y/N/NA   | Y/N/NA              |   |   |                              |
| 57    | 845                    | Y                                   | <0.5                 | Y   | 2.0                  | Y  | N                   | Y | Foundation inspection during construction |                              |
| 58    | 848                    | Y                                   | 2.0                  | Y   | <0.5                 | Y  | N                   | Y | Foundation inspection during construction |                              |
| 59    | 888                    | Y                                   | 2.5                  | Y   | <0.5                 | Y  | N                   | Y | Foundation inspection during construction |                              |
| 60    | 1060                   | Y                                   | 3.0                  | N   | -                    | Y  | N                   | Y | Foundation inspection during construction |                              |
| 61    | 1274                   | Y                                   | 3.0                  | N   | -                    | Y  | N                   | Y | Foundation inspection during construction |                              |
| 62    | 944                    | Y                                   | 3.0                  | Y   | 0.5                  | Y  | N                   | N | Foundation inspection during construction |                              |
| 63    | 1140                   | Y                                   | <0.5                 | Y   | 1.0                  | Y  | N                   | N | Foundation inspection during construction |                              |
| 64    | 853                    | N                                   | -                    | Y   | 1.0                  | Y  | N                   | N | Foundation inspection during construction |                              |
| 65    | 1697                   | Y                                   | 0.5                  | Y   | 0.5                  | Y  | N                   | Y | Foundation inspection during construction |                              |
| 66    | 1355                   | Y                                   | 0.5                  | Y   | 0.5                  | Y  | N                   | Y | Foundation inspection during construction |                              |
| 67    | 921                    | Y                                   | 0.5                  | Y   | 0.5                  | Y  | N                   | Y | Foundation inspection during construction |                              |
| 68    | 842                    | Y                                   | 0.5                  | N   | -                    | Y  | N                   | Y | Foundation inspection during construction |                              |
| 69    | 888                    | Y                                   | 0.5                  | N   | -                    | Y  | N                   | Y | Foundation inspection during construction |                              |
| 70    | 1530                   | Y                                   | 2.0                  | N   | -                    | Y  | N                   | Y | Foundation inspection during construction |                              |

## Lynley Park Residential Subdivision - Stage 1a, Omokoroa

### Summary of Geotechnical Data/Recommendations/Requirements for Individual Lots

| Lot # | Area (m <sup>2</sup> ) | Subsurface Data                     |                      |   |                      | Foundations  |                     |   | Building line restriction?<br><br>Y/N | Recommendations/restrictions              |
|-------|------------------------|-------------------------------------|----------------------|---|----------------------|--|---------------------|---|---------------------------------------|---|
|       |                        | Subdivision filling<br>(TOTAL FILL) |                      | Natural topography<br>earthworked?<br>(TOTAL CUT) |                      | Conventional<br>shallow<br>foundation to<br>NZS<br>3604:1999 | Specific<br>design? |   |                                       |   |
|       |                        |                                     |                      |   |                      |  |                     |   |                                       |   |
|       |                        | Y/N                                 | Average<br>Depth (m) | Y/N   | Average<br>Depth (m) | Y/N/NA   | Y/N/NA              |   |                                       |   |
| 73    | 849                    | Y                                   | <0.5                 | N   | -                    | Y  | N                   | N | Y                                     | Foundation inspection during construction |
| 74    | 834                    | Y                                   | <0.5                 | N   | -                    | Y  | N                   | N | Y                                     | Foundation inspection during construction |
| 75    | 949                    | N                                   | -                    | N   | -                    | Y  | N                   | N | Y                                     | Foundation inspection during construction |
| 76    | 880                    | N                                   | -                    | Y   | 0.5                  | Y  | N                   | N | Y                                     | Foundation inspection during construction |
| 77    | 754                    | N                                   | -                    | Y   | 1.0                  | Y  | N                   | N | Y                                     | Foundation inspection during construction |
| 78    | 794                    | Y                                   | <0.5                 | Y   | 1.5                  | Y  | N                   | N | Y                                     | Foundation inspection during construction |
| 79    | 783                    | Y                                   | <0.5                 | N   | -                    | Y  | N                   | N | N                                     | Foundation inspection during construction |
| 80    | 768                    | N                                   | -                    | N   | -                    | Y  | N                   | N | N                                     | Foundation inspection during construction |
| 81    | 779                    | Y                                   | <0.5                 | N   | -                    | Y  | N                   | N | N                                     | Foundation inspection during construction |
| 82    | 870                    | Y                                   | 1.0                  | N   | -                    | Y  | N                   | N | N                                     | Foundation inspection during construction |
| 83    | 988                    | Y                                   | 1.5                  | Y   | 0.5                  | Y  | N                   | N | Y                                     | Foundation inspection during construction |
| 84    | 822                    | Y                                   | <0.5                 | Y   | 1.5                  | Y  | N                   | N | Y                                     | Foundation inspection during construction |



## PRODUCER STATEMENT — CONSTRUCTION

### CONTRACTOR'S CERTIFICATE UPON COMPLETION OF SUBDIVISIONAL WORK

ISSUE BY: A & R (B.H.) Ltd  
(Contractor)

TO: Durham Property Investments Ltd  
(Principal)

TO BE SUPPLIED TO: Western Bays District Council  
(Territorial Authority)

IN RESPECT OF: Earthworks and Butress drains for stage 1 as defined in CK's final Report  
(Description of subdivisional work)

AT: 313 Omokoroa Road  
(Address)

A & R (B.H.) Ltd has contracted to Durham Property Investments Ltd  
(Contractor) (Principal)

to carry out and complete certain subdivisional works in accordance with a contract, titled Lynley Park  
Reference No: D1176 (CKL Survey) ("Lynley Park")

I, D. Rossmore a duly authorised representative of:  
(Duly Authorised Agent)

A & R (B.H.) Ltd  
(Contractor)

herby certify that A & R (B.H.) Ltd has carried out and completed the Subdivisional works, other than those outstanding works listed below, in accordance with the contract. Subject to Client's instruction, to place landscape fill in reserve & embankment areas of lots 31-45 Date Friday, 25 November 2005  
(Signature of Authorised Agent on behalf of)

D. Rossmore  
(Contractor)

P.O. Box 5161

Hamilton

Outstanding Works

Permanent Pond & associated Stormwater  
Retention Wall & Rockfill

Version: 3

\\Server01\projects\24001\Lynley Park\Quality\QC11 Contractor Producer statement A & R 1.doc

25/11/05


---

## **Appendix B:     Figures**

- **Figure 1**
- **Figure 2**
- **Figure 3**

—

10



|            |           |
|------------|-----------|
| DATE       | 5/11/2005 |
| DRAWN      | SMJ       |
| CHECKED    | SMJ       |
| APPROVED   | SMJ       |
| CAD FILE   | 5/11/2005 |
| SCALE      | 1 in 1000 |
| PROJECT NO | 5/11/2005 |

## LYNLEY PARK SUBDIVISION



## STAGE 1A

## Test Location Plan











**Tonkin & Taylor**  
Environmental & Engineering Consultants  
Dunedin Christchurch  
Dunedin Christchurch  
Dunedin Christchurch

DRAWN: [Signature]  
CHECKED: [Signature]  
APPROVED: [Signature]  
CABLE: [Signature]  
PROJECT: [Signature]  
SCALE: 1 in 1000  
PROJECT NO: 60619

LYNLEY PARK SUBDIVISION  
STAGE 1A  
Test Location Plan

Fig No Figure 1





**Tonkin & Taylor**  
Environmental & Engineering Consultants

|  |                                       |
|--|---------------------------------------|
| <input checked="" type="checkbox"/> Auckland | <input type="checkbox"/> Christchurch |
| <input type="checkbox"/> Hamilton            | <input type="checkbox"/> Dunedin      |
| <input type="checkbox"/> Nelson              | <input type="checkbox"/> Whangarei    |
| <input type="checkbox"/> Tauranga            | <input type="checkbox"/> Wellington   |

|   |     |        |
|---|-----|--------|
| DRAWN   | smb | Nov.05 |
| DRAFTING CHECKED  | gib | Feb.06 |
| APPROVED  | gib | Feb.06 |
| PROFILE :<br>\Cut&fill, CompRep.dwg<br>SCALES (AT A3 SIZE)<br>1 in 1000 |     |        |
| PROJECT No.   |     | 10619  |

LYNLEY PA  
ST  
Test L

FIG. No. Figure 3



**Legend**

- Nuclear demarcator tests
- Fill extents
- Landscape fill
- Building Restriction Line



**Tonkin & Taylor**  
Engineering Consultants  
Environment & Planning  
Auckland  
Dunedin  
Wellington  
Christchurch  
Dunedin  
Wellington

|                 |   |    |     |
|-----------------|---|----|-----|
| DOWN            | DATE  | BY | NO. |
| DRAWING CHECKED | 22/02/2006  | 10 | 10  |
| APPROVED        |   |    |     |
| CAD FILE        | C:\Users\josh\Documents\Projects\22022006\10-10-37 a.m\fig2.dwg |    |     |
| SCALE           | 1 in 1000   |    |     |
| PROJECT NO.     | 505 19  |    |     |

**LYNLEY PARK SUBDIVISION**  
**STAGE 1A**  
**Test Location Plan**

FIG. NO. **Figure 2**

## **Appendix C:     Field Density Tests**

Brett Harland  
A & R Contractors Ltd  
P O Box 3004 Greerton  
Tauranga

**Attention:** Mr B Harland

|                          |                 |             |
|--------------------------|-----------------|-------------|
| RE :                     | Contract Name:  | Lynley Park |
|                          | Sample Source   | On Site     |
|                          | Contract / No.: | Unknown     |
| Quality Control Testing: |                 | Bulk Fill   |

|                       |                      |
|-----------------------|----------------------|
| Test Completion Date: | 31/01/06             |
| Lab Reference:        | TGA0007.14 34TL      |
| Report No:            | 01/06/94/A           |
| Order / Tender No:    | N/A                  |
| Tested By:            | R McGee & G Khokhlov |
| Sample By:            | Richard McGee        |
| Sample Method:        | N/A                  |
| Sample No.:           | 2548                 |
| Date Sampled:         | 27/01/06             |
| Date Received:        | 27/01/06             |
| Date Reported:        | 31/01/06             |
| Sample Condition:     | Natural              |
| Page:                 | 1 of 2               |

## Client Request

To carry out in-situ density tests using Nuclear surface moisture-density gauge, shear stress and laboratory water content determinations on the bulk fill material at Lynley Park

### Test Standards

NZS 4407 : 1991

### Method of testing and sampling road aggregates

### Test 4.2.1

Method using a Nuclear Surface Moisture - Density Gauge-Direct Transmission Mode

NZS 4402 : 1986

### Method of testing soils for Civil Engineering purposes

## Test 2.1

### Determination of the water content

**In House:**

## Operating procedures for the uses of Geotechnics Torque Head

## Test Results

[illegible]

## Notes

- 1 N.D.M = Nuclear Densometer Measurement  $t/m^3$
- 2 Oven = Standard oven method
- 3 Air Voids & Total Voids are calculated using oven water contents & the corrected dry density
- 4 Solid Density is assumed to be =  $2.65 \text{ } t/m^3$
- 5 All Nuclear Densometer Measurements are at the depth of 300mm
- 6 All test locations were chosen by Richard McGee.

**THIS REPORT MAY ONLY BE REPRODUCED IN FULL**

Checked By:

**Richard McGee**  
**Laboratory Supervisor**

Date: 3-1-06 Approved Signatory:

**Hayden Evans**  
**Laboratory Manager**

Date: 31-01-2025

Date 08/11/05

**Version :**

**File Name:**

#### Test 4.2.1 Method using a Nuclear Surface Moisture - Density Gauge-Direct Transmission Mode



All tests reported herein have been performed in accordance with the laboratory's scope of accreditation



# ECES

Evans Civil Engineering Services Ltd

14 Atkins Way Telephone: (07) 544-4418  
Ohauiti Rd Facsimile: (07) 544-5568  
Tauranga

Dolph Rassmussen  
A & R Contractors Ltd  
P O Box 3004 Greerton  
Tauranga

Attention: Mr D Rassmussen

RE : Contract Name: Lynley Park  
Sample Source: On Site  
Contract / No.: Unknown  
Quality Control Testing: Bulk Fill

Test Completion Date: 20/01/06  
Lab Reference: TGA0007.14 33TL  
Report No: 01/06/64/A  
Order / Tender No: N/A  
Tested By: Richard McGee  
Sample By: Richard McGee  
Sample Method: N/A  
Sample No.: 2523  
Date Sampled: 16/01/06  
Date Received: 16/01/06  
Date Reported: 20/01/06  
Sample Condition: Natural  
Page: 1 of 2

## Client Request

To carry out in-situ density tests using Nuclear surface moisture-density gauge, shear stress and laboratory water content determinations on the bulk fill material at Lynley Park

## Test Standards

NZS 4407 : 1991 Method of testing and sampling road aggregates  
Test 4.2.1 Method using a Nuclear Surface Moisture - Density Gauge-Direct Transmission Mode  
NZS 4402 : 1986 Method of testing soils for Civil Engineering purposes  
Test 2.1 Determination of the water content  
In House: Operating procedures for the uses of Geotechnics Torque Head

## Test Results

| Test No.      | Location Northing | Location Easting | Depth Of Fill | N.D.M Wet Density t/m <sup>3</sup> | N.D.M Dry Density t/m <sup>3</sup> | N.D.M Water Content % | Oven Water Content % | Corrected Dry Density t/m <sup>3</sup> | Total Voids % | Air Voids % | Shear Stress (Kpa) |
|---------------|-------------------|------------------|---------------|------------------------------------|------------------------------------|-----------------------|----------------------|--|---------------|-------------|--------------------|
| Lot 58        | 6389824           | 2777495          | Finish Level  | 1.71                               | 1.26                               | 35.5                  | 33.3                 | 1.28                                   | 51.7          | 9.0         | Refusal            |
| Lot 59        | 6389842           | 2777475          | Finish Level  | 1.70                               | 1.24                               | 37.0                  | 33.7                 | 1.27                                   | 52.0          | 9.1         | Refusal            |
| Lot 60        | 6389857           | 2777465          | Finish Level  | 1.61                               | 1.16                               | 39.0                  | 29.5                 | 1.25                                   | 53.0          | 16.2        | Refusal            |
| Lot 61        | 6389867           | 2777449          | Finish Level  | 1.60                               | 1.24                               | 29.5                  | 29.7                 | 1.24                                   | 53.4          | 16.7        | Refusal            |
| Pond Bund (1) | 6389929           | 2777986          | RL9.00        | 1.61                               | 0.99                               | 63.5                  | 33.3                 | 1.21                                   | 54.3          | 14.0        | Refusal            |
| Pond Bund (2) | 6389913           | 2777996          | RL9.00        | 1.63                               | 0.99                               | 64.5                  | 33.0                 | 1.22                                   | 53.9          | 13.5        | Refusal            |
|               |                   |                  |               |                                    |                                    |                       |                      |  |               |             |                    |
|               |                   |                  |               |                                    |                                    |                       |                      |  |               |             |                    |
|               |                   |                  |               |                                    |                                    |                       |                      |  |               |             |                    |
|               |                   |                  |               |                                    |                                    |                       |                      |  |               |             |                    |
|               |                   |                  |               |                                    |                                    |                       |                      |  |               |             |                    |
|               |                   |                  |               |                                    |                                    |                       |                      |  |               |             |                    |
|               |                   |                  |               |                                    |                                    |                       |                      |  |               |             |                    |

## Notes

- 1 N.D.M = Nuclear Densometer Measurement t/m<sup>3</sup>
- 2 Oven = Standard oven method
- 3 Air Voids & Total Voids are calculated using oven water contents & the corrected dry density
- 4 Solid Density is assumed to be = 2.65 t/m<sup>3</sup>
- 5 All Nuclear Densometer Measurements are at the depth of 300mm
- 6 All test locations were chosen by Richard McGee.

THIS REPORT MAY ONLY BE REPRODUCED IN FULL

Checked By:

Richard McGee  
Laboratory Supervisor

Date: 20-1-06 Approved Signatory:

Hayden Evans  
Laboratory Manager

Date: 20-1-06

Date

08/11/05

Version :

2

File Name:

Test 4.2.1 Method using a Nuclear Surface Moisture - Density Gauge-Direct Transmission Mode



All tests reported herein have been performed in accordance with the laboratory's scope of accreditation



Russell Pemberton  
Pemberton Group  
P O Box 5161  
Hamilton

**Attention:** Mr R Pemberton

|                          |             |
|--------------------------|-------------|
| RE : Contract Name:      | Lynley Park |
| Sample Source            | On Site     |
| Contract / No.:          | Unknown     |
| Quality Control Testing: | Bulk Fill   |

|                       |                    |
|-----------------------|--------------------|
| Test Completion Date: | 18/11/05           |
| Lab Reference:        | TGA0067.01 32TL    |
| Report No:            | 11/05/40/A         |
| Order / Tender No:    | N/A                |
| Tested By:.           | R McGee & T Barnes |
| Sample By:            | Richard McGee      |
| Sample Method:        | N/A                |
| Sample No.:           | 2344               |
| Date Sampled:         | 15/11/05           |
| Date Received:        | 15/11/05           |
| Date Reported:        | 18/11/05           |
| Sample Condition:     | Natural            |
| Page:                 | 1 of 1             |

## Client Request

To carry out in-situ density tests using Nuclear surface moisture-density gauge, shear stress and laboratory water content determinations on the bulk fill material at Lynley Park

### Test Standards

NZS 4407 : 1991

### Test 4.2.1

NZS 4402 : 1986

## Test 2.1

**In House:**

## Test Results

### Method of testing and sampling road aggregates

Method using a Nuclear Surface Moisture - Density Gauge-Direct Transmission Mode

**Method of testing soils for Civil Engineering purposes**

#### Determination of the water content

### Operating procedures for the uses of Geotechnics Torque Head

[illegible]

## Notes

- 1 N.D.M = Nuclear Densometer Measurement  $t/m^3$
- 2 Oven = Standard oven method
- 3 Air Voids & Total Voids are calculated using oven water contents & the corrected dry density
- 4 Solid Density is assumed to be =  $2.65 t/m^3$
- 5 All Nuclear Densometer Measurements are at the depth of 300mm
- 6 All test locations were chosen by Richard McGee.
- 7 Test No.s 1A, 2A, 3A waiting for the co-ordinates from Russell Pemberton
- 8 Test No. 4A 14m from road boundary and 10m from boundary of Lots 59/60 Shear Vanes In Lot 60
- 9 Test No. 5A 13m from road boundary and 11m from boundary of Lots 59/60 Shear Vanes in Lot 59
- 10 Test No. 6A 12m from road boundary and 12m from boundary of Lots 58/59 Shear Vanes in Lot 58

THIS REPORT MAY ONLY BE REPRODUCED IN FULL

Checked By:

Richard McGee  
Laboratory Supervisor

Date: 18-11-05

Approved Signatory:

Hayden Evans  
Laboratory Manager

Date  
Version :  
File Name:

08/11/05

2

T

Test 4.2.1 Method using a Nuclear Surface Moisture - Density Gauge-Direct Transmission Mode



All tests reported herein have been performed in accordance with the laboratory's scope of accreditation



14 Atkins Way Telephone: (07) 544-4418  
Ohauiti Rd Facsimile: (07) 544-5568  
Tauranga

**All tests reported herein have been performed in accordance with the laboratory's scope of accreditation.**



# ECES

**Evans Civil Engineering Services Ltd**

14 Atkins Way  
Ohauiti Rd  
Tauranga

Telephone:  
Facsimile:  
E-mail:

(07) 544-4418  
(07) 544-5568  
hcevans@bop.quik.co.nz

Jolph Rasmussen  
- & R. Contractors Ltd  
PO Box 253  
aerog

Attention: Mr D Rasmussen

|                          |             |
|--------------------------|-------------|
| E : Contract Name:       | Lynley Park |
| Sample Source            | Insitu      |
| Contract / No.:          | Unknown     |
| Quality Control Testing: | Bulk Fill   |

|                       |                 |
|-----------------------|-----------------|
| Test Completion Date: | 18/10/2004      |
| Lab Reference:        | TGA0007.14 14TL |
| Report No:            | 10/04/08/A      |
| Order / Tender No:    | Nil             |
| Tested By:            | Hayden Evans    |
| Sample By:            | Hayden Evans    |
| Sample Method:        | N/A             |
| Sample No.:           | 1583            |
| Date Sampled:         | 14/10/2004      |
| Date Received:        | 14/10/2004      |
| Date Reported:        | 18/10/2004      |
| Sample Condition:     | Natural         |
| Page:                 | 1 of 1          |

## Client Request

intend determinations on the bulk fill material at Lynley Park

### Test Standards

S 4407 : 1991

 $\mu = 2.1$ 

42:02:1986

13

### Test Results

### Method of testing and sampling road aggregates

Method using a Nuclear Surface Moisture - Density Gauge-Direct Transmission Mode

Method of testing soils for Civil Engineering purposes  
Determination of the water content

### Determination of the water content

Operating procedures for the uses of Geotechnics Torque Head

| Test | Location   |            | RL     | N.D.M.                          | N.D.M.                          | N.D.M.             | Oven               | Corrected                       | Total      | Air        | Shear Stress<br><br>(Kpa) |
|------|------------|------------|--------|---------------------------------|---------------------------------|--------------------|--------------------|---------------------------------|------------|------------|---------------------------|
|      | Easting    | Northing   |        | Wet Density<br>t/m <sup>3</sup> | Dry Density<br>t/m <sup>3</sup> | Water Content<br>% | Water Content<br>% | Dry Density<br>t/m <sup>3</sup> | Voids<br>% | Voids<br>% |                           |
| 79A  | 261431.976 | 711730.322 | 35.432 | 1.62                            | 1.02                            | 59.0               | 65.6               | 0.98                            | 63.2       | -0.8       | 156, 179, 165             |
| 81A  | 261438.381 | 711715.158 | 34.875 | 1.65                            | 1.11                            | 49.5               | 53.8               | 1.07                            | 59.5       | 1.8        | 205, 193, 176             |
| 82A  | 261454.72  | 711725.876 | 33.335 | 1.63                            | 1.02                            | 59.5               | 69.0               | 0.96                            | 63.7       | -2.8       | 162, 170, 162             |
| 83A  | 261420.065 | 711723.96  | 34.4   | 1.56                            | 0.96                            | 62.0               | 54.8               | 1.01                            | 62.0       | 6.8        | 225, 182, 185             |
|      | 261428.87  | 711707.288 | 33.26  | 1.65                            | 1.05                            | 57.0               | 59.7               | 1.03                            | 61.1       | -0.5       | 170, 170, 156             |
|      |            |            |        |                                 |                                 |                    |                    |                                 |            |            |                           |
|      |            |            |        |                                 |                                 |                    |                    |                                 |            |            |                           |
|      |            |            |        |                                 |                                 |                    |                    |                                 |            |            |                           |
|      |            |            |        |                                 |                                 |                    |                    |                                 |            |            |                           |
|      |            |            |        |                                 |                                 |                    |                    |                                 |            |            |                           |
|      |            |            |        |                                 |                                 |                    |                    |                                 |            |            |                           |
|      |            |            |        |                                 |                                 |                    |                    |                                 |            |            |                           |
|      |            |            |        |                                 |                                 |                    |                    |                                 |            |            |                           |
|      |            |            |        |                                 |                                 |                    |                    |                                 |            |            |                           |
|      |            |            |        |                                 |                                 |                    |                    |                                 |            |            |                           |
|      |            |            |        |                                 |                                 |                    |                    |                                 |            |            |                           |
|      |            |            |        |                                 |                                 |                    |                    |                                 |            |            |                           |
|      |            |            |        |                                 |                                 |                    |                    |                                 |            |            |                           |
|      |            |            |        |                                 |                                 |                    |                    |                                 |            |            |                           |
|      |            |            |        |                                 |                                 |                    |                    |                                 |            |            |                           |

1 N.D.M = Nuclear Densometer Measurement t/m<sup>3</sup>  
2 W.C = Water Content %

1.  $M$  = Nuclear Densometer Measurement  $t/m^3$   
2.  $\rho$  = Standard

2.  $\sigma_n$  = Standard oven method

☐ Air Voids & Total Voids are calculated using oven water contents & the corrected dry density  
☐ Solid Density is assumed to be =

5 All Nuclear Densometer Measurements  $2.65 \text{ t/m}^3$

All test locations were chosen by the test

All test locations were chosen by the contractor.



All tests reported herein have been performed in accordance with the laboratory's scope of accreditation

REPORT MAY ONLY BE REPRODUCED EXCEPT IN FULL

Checked By:

Richard McGee  
Laboratory Supervisor  
23/10/01

Date: 18-10-04

Approved Signatory:

Hayden Evans  
Laboratory Manager

Date: 18-10-04

sion :

1 me:

Test 4.2.1 Method using a Nuclear Surface Moisture - Density Gauge-Direct Transmission Mode



# ECES

Evans Civil Engineering Services Ltd

14 Atkins Way Telephone: (07) 544-4418  
Ohauti Rd Facsimile: (07) 544-5568  
Tauranga E-mail: hcevans@bop.quik.co.nz

Dolph Rasmussen  
A & R Contractors Ltd  
PO Box 253  
Paeroa

Attention: Mr D Rasmussen

RE: Contract Name: Lynley Park  
Sample Source: Insitu  
Contract / No.: Unknown  
Quality Control Testing: Bulk Fill

Test Completion Date: 28/10/2004  
Lab Reference: TGA0007.14 15TL  
Report No: 10/04/24/A  
Order / Tender No: Nil  
Tested By: Hayden Evans  
Sample By: Hayden Evans  
Sample Method: N/A  
Sample No.: 1598  
Date Sampled: 21/10/2004  
Date Received: 21/10/2004  
Date Reported: 28/10/2004  
Sample Condition: Natural  
Page: 1 of 1

## Client Request

To carry out in-situ density tests using Nuclear surface moisture-density gauge, shear stress and laboratory water content determinations on the bulk fill material at Lynley Park

## Test Standards

NZS 4407 : 1991

Method of testing and sampling road aggregates

Test 4.2.1

Method using a Nuclear Surface Moisture - Density Gauge-Direct Transmission Mode

AS 102 : 1986

Method of testing soils for Civil Engineering purposes

Test 2.1

Determination of the water content

In House:

Operating procedures for the uses of Geotechnics Torque Head

## Test Results

| Test No. | Location      | Depth Of Fill | N.D.M Wet Density t/m <sup>3</sup> | N.D.M Dry Density t/m <sup>3</sup> | N.D.M Water Content % | Oven Water Content % | Corrected Dry Density t/m <sup>3</sup> | Total Voids % | Air Voids % | Shear Stress (Kpa) |
|----------|---------------|---------------|------------------------------------|------------------------------------|-----------------------|----------------------|--|---------------|-------------|--------------------|
| 84A      | 261559 712126 | 28.392        | 1.68                               | 1.10                               | 52.0                  | 50.2                 | 1.12                                   | 57.8          | 1.6         | 167, 170, 185      |
| 85A      | 261568 712147 | 28.162        | 1.67                               | 1.15                               | 45.5                  | 43.4                 | 1.17                                   | 55.9          | 5.3         | 130, 144, 173      |
| 86A      | 261592 712174 | 28.696        | 1.65                               | 1.05                               | 56.0                  | 57.6                 | 1.04                                   | 60.6          | 0.4         | 205, 216, 208      |
| 87A      | 261626 712165 | 29.027        | 1.74                               | 1.18                               | 47.5                  | 40.1                 | 1.24                                   | 53.3          | 3.6         | 133, 166, 173      |
| 88A      | 261614 712145 | 29.94         | 1.79                               | 1.32                               | 35.5                  | 34.0                 | 1.34                                   | 49.5          | 4.1         | 165, 144, 139      |
| 89A      | 261451 711725 | 34.761        | 1.64                               | 1.03                               | 59.0                  | 62.8                 | 1.00                                   | 62.1          | -1.0        | 147, 147, 211      |
| 90A      | 261472 711728 | 34.927        | 1.64                               | 1.12                               | 46.5                  | 39.9                 | 1.17                                   | 55.9          | 9.3         | 141, 170, 150      |
|          |               |               |                                    |                                    |                       |                      |  |               |             |                    |
|          |               |               |                                    |                                    |                       |                      |  |               |             |                    |
|          |               |               |                                    |                                    |                       |                      |  |               |             |                    |
|          |               |               |                                    |                                    |                       |                      |  |               |             |                    |
|          |               |               |                                    |                                    |                       |                      |  |               |             |                    |
|          |               |               |                                    |                                    |                       |                      |  |               |             |                    |
|          |               |               |                                    |                                    |                       |                      |  |               |             |                    |

1 N.D.M = Nuclear Densometer Measurement t/m<sup>3</sup>

2 Oven = Standard oven method

3 Air Voids & Total Voids are calculated using oven water contents & the corrected dry density

4 Solid Density is assumed to be = 2.65 t/m<sup>3</sup>

5 All Nuclear Densometer Measurements are at the depth of 300mm

6 All test locations were chosen by the contractor.



All tests reported herein have been performed in accordance with the laboratory's scope of accreditation

THIS REPORT MAY ONLY BE REPRODUCED EXCEPT IN FULL

Checked By:

*Richard McGee*  
Richard McGee  
Laboratory Supervisor

Date: 28-10-04

Approved Signatory:

*Hayden Evans*  
Hayden Evans  
Laboratory Manager

Date: 23/10/01

Version: 1

File Name: Test 4.2.1 Method using a Nuclear Surface Moisture - Density Gauge-Direct Transmission Mode

**ECES**

Evans Civil Engineering Services Ltd

14 Atkins Way  
Ohauiti Rd  
TaurangaTelephone:  
Facsimile:  
mail:(07) 544-4418  
E: (07) 544-5568  
hceevans@bop.quik.co.nzDolph Rassmussen  
I & R Contractors  
PO Box 253  
Paeroa

Attention: Mr D Rassmussen

Contract Name: Lynley Park  
Sample Source: On Site  
Contract / No.: Unknown  
Quality Control Testing: Bulk FillTest Completion Date: 1/02/2005  
Lab Reference: TGA0007.14 22TL  
Report No: 01/05/57/A  
Order / Tender No: Nil  
Tested By: R McGee/T Barnes  
Sample By: Richard McGee  
Sample Method: N/A  
Sample No.: 1795  
Date Sampled: 26/01/2005  
Date Received: 26/01/2005  
Date Reported: 2/02/2005  
Sample Condition: Natural  
Page: 1 of 1**Client Request**

To carry out in-situ density tests using Nuclear surface moisture-density gauge, shear stress and laboratory water content determinations on the bulk fill material at Lynley Park

**Test Standards**IS 4407 : 1991  
st 4.2.1  
NZS 4402 : 1986Method of testing and sampling road aggregates  
Method using a Nuclear Surface Moisture - Density Gauge-Direct Transmission Mode  
Method of testing soils for Civil Engineering purposes  
Determination of the water content  
Operating procedures for the uses of Geotechnics Torque Head**Test Results**

| Test No. | Location   |            | Depth Of Fill | N.D.M                        |                              |                 | Oven Water Content % | Corrected Dry Density t/m <sup>3</sup> | Total Voids % | Air Voids % | Shear Stress (Kpa) |
|----------|------------|------------|---------------|------------------------------|------------------------------|-----------------|----------------------|--|---------------|-------------|--------------------|
|          | Northing   | Easting    |               | Wet Density t/m <sup>3</sup> | Dry Density t/m <sup>3</sup> | Water Content % |                      |  |               |             |                    |
| 152A     | 711734.984 | 261408.54  | RL37.305      | 1.79                         | 1.32                         | 35.5            | 40.3                 | 1.27                                   | 51.9          | 0.6         | Refusal            |
| 153A     | 711715.59  | 261409.018 | RL34.949      | 1.72                         | 1.30                         | 32.5            | 34.0                 | 1.28                                   | 51.5          | 7.8         | Refusal            |
| 154A     | 711698.711 | 261420.495 | RL33.485      | 1.69                         | 1.15                         | 47.5            | 49.8                 | 1.13                                   | 57.4          | 1.2         | 179, 196, 188      |
| 155A     | 711685.474 | 261434.099 | RL32.408      | 1.69                         | 1.19                         | 41.5            | 47.2                 | 1.15                                   | 56.8          | 2.7         | Refusal            |
| 156A     | 711742.041 | 261452.724 | RL36.793      | 1.82                         | 1.32                         | 38.0            | 43.4                 | 1.27                                   | 52.3          | 0.0         | Refusal            |
| 157A     | 712087.101 | 261629.543 | RL34.174      | 1.70                         | 1.26                         | 35.5            | 47.9                 | 1.15                                   | 56.6          | 1.4         | Refusal            |
| 158A     | 712096.264 | 261657.1   | RL33.954      | 1.71                         | 1.18                         | 44.9            | 49.9                 | 1.14                                   | 56.9          | 0.0         | 156, 175, 167      |
| 159A     | 712127.58  | 261604.976 | RL32.013      | 1.64                         | 1.01                         | 61.6            | 63.5                 | 1.00                                   | 62.2          | 0.0         | Refusal            |
| 160A     | 712142.481 | 261592.348 | RL30.551      | 1.61                         | 0.99                         | 63.2            | 49.2                 | 1.08                                   | 59.3          | 6.2         | 138, 144, 101      |
|          |            |            |               |                              |                              |                 |                      |  |               |             |                    |
|          |            |            |               |                              |                              |                 |                      |  |               |             |                    |
|          |            |            |               |                              |                              |                 |                      |  |               |             |                    |
|          |            |            |               |                              |                              |                 |                      |  |               |             |                    |
|          |            |            |               |                              |                              |                 |                      |  |               |             |                    |

N.D.M = Nuclear Densometer Measurement t/m<sup>3</sup>

Oven = Standard oven method

Air Voids & Total Voids are calculated using oven water contents & the corrected dry density  
Solid Density is assumed to be = 2.65 t/m<sup>3</sup>

5 All Nuclear Densometer Measurements are at the depth of 300mm

6 All test locations were chosen by the contractor.

REPORT MAY ONLY BE REPRODUCED EXCEPT IN FULL

Checked By:

Richard McGee  
Laboratory Supervisor  
23/10/01

Date: 2-2-05

Approved Signatory:

Hayden Evans  
Laboratory Manager

Date: 02-02-05

Revision:

Name:

Test 4.2.1 Method using a Nuclear Surface Moisture - Density Gauge-Direct Transmission Mode

All tests reported  
herein have been  
performed in accordance



# ECES

**Evans Civil Engineering Services Ltd**

14 Atkins Way  
Ohauiti Rd  
Tauranga

Telephone:  
Facsimile:

(07) 544-4418  
(07) 544-5568

Brett Harland  
A & R Contractors Ltd  
P O Box 3004 Greerton  
Tauranga

**Attention:** Mr B Harland

|                          |                 |             |
|--------------------------|-----------------|-------------|
| RE :                     | Contract Name:  | Lynley Park |
|                          | Sample Source   | On Site     |
|                          | Contract / No.: | Unknown     |
| Quality Control Testing: |                 | Bulk Fill   |

|                       |                 |
|-----------------------|-----------------|
| Test Completion Date: | 22/02/2008      |
| Lab Reference:        | TGA0007.14 36TL |
| Report No:            | 02/06/44/A      |
| Order / Tender No:    | N/A             |
| Tested By:            | Richard McGee   |
| Sample By:            | Richard McGee   |
| Sample Method:        | N/A             |
| Sample No.:           | 2608            |
| Date Sampled:         | 21/02/2006      |
| Date Received:        | 21/02/2006      |
| Date Reported:        | 22/02/2006      |
| Sample Condition:     | Natural         |
| Page:                 | 1 of 2          |

### Client Request

To carry out in-situ density tests using Nuclear surface moisture-density gauge, shear stress and laboratory water content determinations on the bulk fill material at Lynley Park

### Test Standards

NZS 4407 : 1991

### Test 4.2.1

NZS 4402 : 1986

## Test 2.1

**In House:**

### Test Results

### Method of testing and sampling road aggregates

Method of testing soils for Civil Engineering purposes

Method of testing soils for Civil Engineering purposes

### Determination of the water content

Operating procedures for the uses of Geotechnics Torque Head

[illegible]

otes

- 1 N.D.M = Nuclear Densometer Measurement  $t/m^3$
- 2 Oven = Standard oven method
- 3 Air Voids & Total Voids are calculated using oven water contents & the corrected dry density
- 4 Solid Density is assumed to be =  $2.65 \text{ } t/m^3$
- 5 All Nuclear Densometer Measurements are at the depth of 300mm
- 6 All test locations were chosen by Richard McGee.

THIS REPORT MAY ONLY BE REPRODUCED IN FULL

Checked By:

Richard McGee  
Laboratory Supervisor  
1/02/2006

Date: 22-2-06

Approved Signatory

Hayden Evans  
Laboratory Manager

Date: 22-2-06

Version :

**File Name:**

Test 4.2.1 Method using a Nuclear Surface Moisture - Density Gauge-Direct Transmission Mode



All tests reported herein have been performed in accordance with the laboratory's scope of accreditation.

## **Appendix D: Earthworks Specification**

## **DURHAM PROPERTY INVESTMENTS LTD**

### **LYNLEY PARK SUBDIVISION**

### **SPECIFICATIONS**

Ref: 60619  
March 2004

Prepared for: DURHAM PROPERTY INVESTMENTS LTD  
Prepared by: Tonkin & Taylor Ltd



## CONTENTS

Page No.

|            |   |            |
|------------|---|------------|
| <b>1.0</b> | <b>GENERAL.....</b>                       | <b>1-1</b> |
| 1.1        | Location.....                             | 1-1        |
| 1.2        | Extent of Contract.....                   | 1-1        |
| 1.3        | Definitions.....                          | 1-1        |
| <b>2.0</b> | <b>BULK EARTHWORKS.....</b>               | <b>2-2</b> |
| 2.1        | Scope.....                                | 2-2        |
| 2.2        | General Requirements.....                 | 2-2        |
| 2.3        | Topsoil Stripping.....                    | 2-2        |
| 2.4        | Cut Operations.....                       | 2-3        |
| 2.5        | Fill Placement.....                       | 2-3        |
| 2.6        | Fill Operations.....                      | 2-4        |
| 2.7        | Compaction Testing.....                   | 2-4        |
| <b>3.0</b> | <b>SUBSOIL DRAINAGE.....</b>              | <b>3-7</b> |
| 3.1        | Scope.....                                | 3-7        |
| 3.2        | Materials.....                            | 3-7        |
| 3.3        | Trenching and Other Open Excavations..... | 3-8        |
| 3.4        | Subsoil Drainage Pipe Installation.....   | 3-8        |
| 3.5        | Backfilling.....                          | 3-8        |
| 3.6        | Inspections and Approvals.....            | 3-9        |



## **1.0 GENERAL**

### **1.1 Location**

The work included in this Contract and to which the Specification and Drawings refer is located at Lynley Park Subdivision, Omokoroa Road, Omokoroa.

### **1.2 Extent of Contract**

The extent of the contract is as shown on the drawings prepared by CKL Ltd.

### **1.3 Definitions**

The following definitions shall apply to this section of the specification only:

Engineer : The owner's representative, Russell Pemberton of Pemberton Group.

Geotechnical Engineer : Tonkin & Taylor Ltd



## 2.0 BULK EARTHWORKS

### 2.1 Scope

This Section sets out the requirements for the completion of bulk earthworks. All work shall be carried out in accordance with Transit New Zealand specification F/1 (1997), except where amended by this specification.

In addition, work shall comply with the requirements of the Environment Bay of Plenty Erosion and Sediment Control Guidelines for Earthworks and the conditions of consent for this project in Volume IV of the contract documents.

### 2.2 General Requirements

#### 2.2.1 Hold Points and Response Times

The Contractor shall give notice to the Engineer for specific points in construction for the purposes of inspection, with the requirements as follows:

- After stripping and prior to placement of fill: minimum of 24 hours notice
- Prior to construction of buried services: a minimum of 24 hours notice
- Backfilling over subsoil drainage: not without written approval of the Engineer

#### 2.2.2 Haul Roads

The Contractor shall construct and maintain all temporary haul roads required to carry out the works. All haul roads shall be located within the site of works. At the completion of the project the Contractor shall rehabilitate haul road areas.

The Contractor shall submit to the Engineer, for his approval, the proposed methodology to gain access to various sections of the site, including any cutting or filling. Temporary haul roads within Structural Fill zones other than those shown on the drawings shall be to the prior approval of the Geotechnical Engineer.

### 2.3 Topsoil Stripping

All turf and organic topsoil shall be stripped from the areas subject to earthworks before other operations commence in these areas. All topsoil shall be stockpiled for future re-use in the locations shown on the Drawings or areas otherwise approved on site by the Engineer. The stockpiles shall have slopes not steeper than 1V:2H and be rounded to conform generally with the surrounding landscape.

The depth of topsoil stripping shall be sufficient to remove all organic material, turf and significant plant roots. Except where limited by boundaries, existing works or other limiting features, stripping shall extend 2 m beyond the limits of areas subject to earthworks or construction. The Contractor shall co-operate with the Engineer ahead of, and during, stripping operations to determine the stripping depth and shall avoid unnecessary over-excavation.

## 2.4 Cut Operations

### 2.4.1 Undercut and Replace

Where shown on the Drawings or where directed by the Geotechnical Engineer, unsuitable material within the fill subgrade shall be undercut to waste and replaced with structural grade filling.

### 2.4.2 Cut to Waste

If the Contractor deems material not fit for the purposes of cut to fill he is to advise the Engineer. At the Engineer's discretion the Contractor shall either, condition then place material as fill or remove material off site.

If instructed by the Engineer, cut material (other than topsoil and that required for fill or backfill) shall be carted to the Principal's nominated dump or removed from site and disposed of. The dumped material shall be track rolled and levelled to the level of the surrounding ground, or as directed.

### 2.4.3 Cut to Fill

All excavated soils (except organic material) is to be placed as fill within the reclamation.

Prior to compaction, all fill material shall be broken into fragments of less than 100 mm. The material shall be spread uniformly in layers of less than 200 mm thickness, and conditioned to an appropriate water content.

The Contractor shall carry out the cut to fill operation so as to optimise drying of wet cut materials.

Fill shall not be spread over surfaces, which have deteriorated from their specified condition. Where necessary, the old surface shall be scarified, conditioned and re-compacted before placing fill. The Contractor shall exclude all organic matter from fills.

## 2.5 Fill Placement

### 2.5.1 General

Prior to compaction, all fill material shall be broken into fragments of less than 100 mm size. The material shall be spread uniformly in layers of less than 200 mm thickness, and conditioned to a water content suitable to achieve the earthfill criteria.

Trafficking and reworking of the fill material shall be minimised at all times, in order to limit strength loss within the sensitive volcanic ash soils.

New fill shall not be spread over surfaces that have deteriorated from their specified condition. Where necessary, the old surface shall be scarified and conditioned and re-compacted before placing new fill. The Contractor shall exclude all organic matter from fills.

### 2.5.2 Equipment

The Contractor shall employ sufficient compaction equipment to achieve the specified compaction. The number and type of plant necessary shall be confirmed by trials. No subsequent changes shall be introduced without the prior approval of the Engineer.

### 2.5.3 Control of Water Content

When soil is to be dried the Contractor shall disc the soil and allow it to dry uniformly to its full depth.

When the soil is to be wetted, this shall be done with sprinkling equipment, ensuring uniform and controlled distribution of water in conjunction with blading and discing. Any costs of drying or wetting will be deemed to be included in the fill rate or other scheduled items. No extra payments will be made.

## 2.6 Fill Operations

The earthworks shall be scheduled to optimise the borrow materials as they become available.

No fill shall be placed on new foundation areas prior to the inspection and approval by the Geotechnical Engineer.

Temporary fill slopes within the fill should be avoided, except at changes in material zoning. The fill should be thoroughly mixed and compacted to ensure the overall fill achieves specified requirements.

If the surface of the existing fill becomes too smooth or too dry to bond to the next lift properly, the fill surface shall be roughened to a depth of at least 75 mm and conditioned for water content as necessary.

Fill shall not be placed over a previous lift that has not achieved specification, or has become contaminated.

Compaction of all material shall be carried out using specialised compaction equipment separate to that used for transportation and spreading.

Fill shall be topsoiled and grassed as soon as possible after reaching the required levels to minimise erosion risk. Repair of any erosion damage shall be to the Engineer's instructions and at no cost to the Principal.

## 2.7 Compaction Testing

Compaction of non-granular (cohesive) fill obtained from project area cuts shall be measured by the Undrained Shear Strength and Maximum Air Voids.

Compacted fill shall meet the requirements given in Tables 2.6.1 and 2.6.2 before any further filling or topsoil is placed on it.

The testing frequency shall be as defined in Table 2.6.2 below, unless confirmed otherwise in writing by the Engineer.

The specific gravity of solid particles to be used in the air voids test shall be determined at the frequency given in Table 2.6.1. Any adjustment to the fill density/air voids test results shall be subject to prior agreement from the Engineer.

In-situ densities and moisture content measures shall be made with a Nuclear Densometer in accordance with NZS 4407:1991 and the manufacturer's instructions. The Contractor shall adjust moisture content values obtained from the Nuclear Densometer to agree as closely as possible with results obtained from oven dried laboratory samples. All reporting of moisture content shall use laboratory test results.

**TABLE 2.6.1 : Compaction Testing**

| Test   | Method   | Notes  |
|--|--|--|
| Vane Shear   | NZ Geotechnical Society Guidelines for Hand-held Shear Vane (2002) | The result shall be taken as the mean of at least 4 No. readings within a area of $\geq 0.5\text{m}^2$ , located within representative zones of the material being tested. |
| Water Content  | NZS4402  |  |
| Dry Density  | NZS4402  |  |
| Air-Voids  | NZS4402  |  |
| Solid Density  | NZS4402  | 1 test per material type, subject to Geotechnical Engineer's written approval, and provided the nature of the fill remains consistent.                                     |
| Notes:   |  |  |
| <ul style="list-style-type: none"> <li>Additional tests should be carried out if the nature of the fill changes, or at the direction of the Engineer.</li> <li>Tests shall be accordance with NZS4402 <i>Methods of Testing Soils for Civil Engineering Purposes</i>, as appropriate.</li> </ul> |  |  |

**TABLE 2.6.2 : Fill Testing Requirements**

| Fill Type  | Test                     | Min. frequency   | Criteria   |
|--|--------------------------|--|--|
| Structural Fill more than 1.0 m below finished level   | Water Content            | 1 per 2,000 m <sup>3</sup>   | Minimum = 35 %<br>Maximum = 60 %                                   |
|  | Air Voids                | 1 per 2,000 m <sup>3</sup>   | Maximum = 10.0 %   |
|  | Undrained Shear Strength | 1 per 500 m <sup>3</sup> ,<br>reducible to 1 per 1000 m <sup>3</sup>                         | Average result $\geq 115$ kPa<br>Any single reading $\geq 110$ kPa |
| Structural Fill less than 1.0 m below finished level   | Water Content            | 1 per 2,000 m <sup>3</sup>   | Minimum = 35 %<br>Maximum = 60 %                                   |
|  | Air Voids                | 1 per 1,000 m <sup>3</sup><br>1 per 1,000 m <sup>2</sup> for filling less than <500 mm thick | Maximum = 8.0 %  |
|  | Undrained Shear Strength | 1 per 500 m <sup>3</sup>   | Average result $\geq 125$ kPa<br>Any single reading $\geq 115$ kPa |
| Non-structural Fill  | Air Voids                | 1 per 3,000 m <sup>3</sup> provided <1000 mm lifts   | Maximum = 14 %   |
|  | Undrained Shear Strength | 1 per 1,000 m <sup>3</sup> , reducible to 1 per 2000 m <sup>3</sup>                          | Average result $\geq 60$ kPa<br>Any single reading $\geq 60$ kPa   |
| Notes:   |                          |  |  |
| <ul style="list-style-type: none"> <li>The frequency of testing will depend on the consistency of fill operations and materials used, and may be varied by the Engineer to obtain sufficient spatial coverage through the depth and extent of the filling.</li> <li>Additional tests should be carried out if the nature of the fill changes, or at the direction of the Engineer.</li> <li>The Engineer and Contractor shall continue to monitor earthworks operations. Once materials are consistent and work is being carried out in a systematic and consistent manner, the Engineer may vary the frequency of testing.</li> </ul> |                          |  |  |

### 3.0 SUBSOIL DRAINAGE

#### 3.1 Scope

This Section sets out the requirements for subsoil drainage, including underfill drains.

All work shall be carried out in accordance with Transit New Zealand specification F/6 (2003) "Specification for geotextile wrapped aggregate subsoil drain construction", except where amended by this specification.

#### 3.2 Materials

**Subsoil Drainpipes :** perforated high density polyethylene (HDPE) pipe of corrugated profile ("Novaflo" or approved equivalent) covered with Filtersok or wrapped in a filter cloth approved by the Engineer. Connection from the subsoil drainage pipe to the specified outlet position shall consist of high density polyethylene (HDPE) pipe of corrugated profile ("Novacoil" or approved equivalent).

**Geotextile :** Non-woven geotextile fabric of type Bidim A24 or equivalent approved, complying with Transit NZ F/7 specification. No geotextile exhibiting tears, rips, or holes shall be used.

**Granular Backfill :** shall comprise be clean durable aggregate, nominally GAP40 or an approved equivalent approved by the Engineer. Random checks on the material may be undertaken by the Engineer to ensure the requirements of the grading envelope are being met. Material with more than 5% silt or clay fines will not be accepted. and when wet sieved in accordance with NZS 4402 Part 1: Test 9B, shall comply with the following grading:

| Standard Sieve<br>Aperture Size | Percentage Passing |
|---------------------------------|--------------------|
| 40                              | 100                |
| 26.5 mm                         | 90 - 100           |
| 13.2 mm                         | 85 - 100           |
| 9.3 mm                          | 80 - 95            |
| 2.36 mm                         | 50 - 70            |
| 1.18 mm                         | 35 - 55            |
| 600 µm                          | 18 - 40            |
| 300 µm                          | 3 - 25             |
| 150 µm                          | 0 - 8              |
| 75 µm                           | 0                  |

Materials not specified are to be of the best quality.

All materials shall be stored and handled in accordance with the manufacturer's specifications, and in a manner that fully minimises the risk of damage.



### 3.3 Trenching and Other Open Excavations

Excavated material shall be stacked at least 600 mm from the edge of the trench. The size of the spoil bank shall be such that there is no danger to the stability of the trench. Avoid blocking any road or footpath.

Surplus material shall be disposed of to the onsite disposal area as directed by the Engineer. Surplus material not cleared by the Contractor may be removed by others at the Contractor's expense to the satisfaction of the Engineer.

The maximum length of open trench may not normally exceed 10 m ahead of pipe laying or such lesser distance as may be determined in view of the nature of the ground. Lengths greater than 10 m may only be open with the approval of the Engineer.

The Contractor shall direct his operations to avoid excavating beyond designated profiles. Any over-excavation beyond these profiles carried out without the direction of the Engineer shall be made good, to the direction of the Engineer, with compacted fill of equal quality to that designated to cover the original excavated profile, at no cost to the Principal.

### 3.4 Subsoil Drainage Pipe Installation

The Contractor shall not commence laying or bedding until the foundation in the trench has been inspected and approved by the Engineer.

Subsoil drains shall be installed in the location and at the levels shown on the drawings. Trenches shall be trimmed true to grade and line to a width of at least that shown on the drawings and the gradient of the bottom of the trench shall be not less than 1:60. The minimum depth of granular backfilling shall be in accordance with the drawings.

The geotextile shall be placed in the trench so as to conform loosely to the shape of the trench. Care shall be taken to avoid projections which could stretch and damage the geotextile. Longitudinal joints shall be limited to one overlap. Transverse joints shall comprise a splice length of at least 500 mm.

At the uphill end of a subsoil drain the perforated pipe shall be brought up the end of the trench and terminated 1.0 m below ground level. The end of the pipe shall be folded back on itself and tied together.

### 3.5 Backfilling

Subsoil drains shall be backfilled using GAP40 or an approved equivalent. The upper 0.5 m of each trench shall be backfilled with compacted silt-clay soil from the trench excavation to form a seal against the ingress of surface water. Compaction of the clay seal is to be by tamping with the bucket of the excavation machine and track-rolling with a traxcavator or similar plant. Care shall be taken to not crush the subsoil pipe.

Beneath road carriageways, backfill shall be placed up to the proposed subgrade level. Over the carriageway width the backfill shall be compacted to a depth of 0.5 m below subgrade level using a mechanical wacker or approved equivalent.

### 3.6 Inspections and Approvals

Before any trench excavation is commenced or fill is placed in any area, the Engineer shall be given sufficient notice prior to commencement so that he or his representative can inspect the excavation material to see that the work undertaken meets the Specification requirements. No excavation or backfilling shall be undertaken in the area until the inspections have been made and the Engineer, after further work has been undertaken by the Contractor as necessary, has approved the commencement of excavation or backfilling works. Periodic inspection may be undertaken by the Engineer or his representative at random intervals during the period of the Contract.

J:\T&T Hamilton jobs\Lynley Park\ajc 60619.Spe.doc





| PLANT SCHEDULE               |                    |                        |
|------------------------------|--------------------|------------------------|
| TREE SPECIES                 | GRADE              | NUMBER<br>Sheet<br>TWO |
| (P1) Pittavnia sp            | Pl 40<br>Overplant | 4                      |
| (P2) Liquidambar             | Pl 40<br>Overplant | 1                      |
| (P3) Magnolia grandiflora    | Pl 40<br>Overplant | 5                      |
| (P4) Quercus sp              | Pl 40<br>Overplant | 5                      |
| (P5) Eucalyptus ficifolia    | Pl 40<br>Overplant | 5                      |
| (P6) Corynocarpus laevigatus | Pl 40<br>Overplant | 11                     |
| (P7) Knightia excelsa        | Pl 40<br>Overplant | 13                     |
| (P8) Metrosideros excelsa    | Pl 40<br>Overplant | 27                     |
| (P9) Vitex lucida            | Pl 40<br>Overplant | 3                      |
| (P10) Dysosmum spectabile    | Pl 40<br>Overplant | 6                      |

| TOTAL PLANTED AREAS |   | CENTERS          |
|---------------------|---|------------------|
|                     | Planted in natural vegetation patterns, undisturbed with scattered natives.   | 1.5 - 2.5 m      |
|                     | Cypressus debilis<br>Woodfordia frutescens<br>Use native plants and trees in the deciduous, western species with not near road.   | 1.5 - 4 m        |
|                     | Native sp.<br>NZ Natives.<br>Planted in natural patterns, undisturbed with scattered natives. Use native plants and trees in the deciduous, western species with not near road. | 1.5 m (randomly) |

**GENERAL NOTES**

The Planting Plan has been prepared as a resource consent requirement to help mitigate the visual impact of this development.

Final planting layout will be determined on site to fit with site contours.

Ensure that the final placement of specimen trees provides for a 2 m set back from reserve boundary.

Planting callouts should follow related practices and steps as per the landscape plan. It is important the view shafts from the reserve are clear and that the reserve retains areas of open space.

Ensure that all open grassed areas on the reserve are mowed. Any areas that are unable to be mowed are to be planted with natives. These areas can be vegetated after earthworks completion.

**SITE PREPARATION**

All planting area excavations shall be shaped and finished and any drainage required and soil mix supplied and placed, if necessary, to ensure the optimum growth of the trees and plants.

At least 100 mm of topsoil shall be provided prior to planting.

Ensure all existing grass, weeds and exotic shrubs are removed.

**PLANTING**

All trees and plants shall be of best nursery stock, healthy and vigorous and free from pests and diseases and free from physical damage.

All trees and plants shall be planted to the same height in the soil as they were in the nursery.

All trees and plants shall be planted with a root collar and shall be thoroughly watered in immediately following planting.

All trees and plants shall be planted with a root collar and shall be thoroughly watered in immediately following planting.




**MAINTENANCE**

Following the completion of planting, the planted areas are to be maintained for a period of 12 months. During this period, weeds and grasses shall be removed for a period of 12 months or until plants are successfully established.

Any trees or plants that are found to be dead or dying shall be removed and replaced with a similar species and/or maintained.

Herbicides must be used with caution and in strict accordance with manufacturer's instructions.

No trees or plants shall experience stress from lack of water and / or nutrient deficiencies throughout the maintenance period.

| TOTAL MIXED AREAS   | CENTRES          |
|---|------------------|
|  | 1.5 - 2.5 m      |
|  | 1.5 - 4 m        |
|  | 1.5 m (randomly) |

1.5 - 2.5 m

1.5 - 4 m

1.5 m (randomly)

1.5 - 2.5 m

1.5 - 4 m

1.5 m (randomly)

1.5 - 2.5 m

1.5 - 4 m

1.5 m (randomly)

1.5 - 2.5 m

1.5 - 4 m

1.5 m (randomly)

1.5 - 2.5 m

1.5 - 4 m

1.5 m (randomly)

1.5 - 2.5 m

1.5 - 4 m

1.5 m (randomly)

1.5 - 2.5 m

1.5 - 4 m

1.5 m (randomly)

1.5 - 2.5 m

1.5 - 4 m

1.5 m (randomly)

1.5 - 2.5 m

1.5 - 4 m

1.5 m (randomly)

# GENERAL NOTES

The Planting Plan has been prepared as a resource consent requirement to help mitigate the visual impact of the development.

Final planting layout will be determined on site to fit with site context.

Ensure that the final placement of specimen trees provides for a 2m setback from reserve boundary.

Planting patterns should follow natural ground and water around it.

It is important the view from the reserve are well and that the reserve reflects areas of open space.

Ensure that all open grassed areas on the reserve are mowed. Any trees that are unable to be mowed are to be planted with native trees.

These areas can be mowed after development completion.

## SITE PREPARATION

All planting area excavations shall be shaped and finished and any drainage required and not yet supplied and placed, if necessary, to ensure that the ground is level and suitable for planting.

All compacted ground in the planting area to be broken prior to planting.

Ensure all existing grass, weeds and exotic shrubs are removed.

## PLANTING

All trees and plants shall be of best nursery stock, healthy and vigorous and free from pests and diseases and shall be planted in the same height in the soil as at the nursery.

All trees and plants shall be planted in the same height in the soil as at the nursery.











All trees and plants shall be planted in the same height in the soil as at the nursery.

All trees and plants shall be planted in the same height in the soil as at the nursery.

All trees and plants shall be planted in the same height in the soil as at the nursery.

All trees and plants shall be planted in the same height in the soil as at the nursery.

All trees and plants shall be planted in the same height in the soil as at the nursery.

| TREE SPECIES  | GRADE | NUMBER OF PLANTS |
|---|-------|------------------|
|   | Pt 40 | 3                |
|  | Pt 40 | 6                |
|  | Pt 40 | 5                |
|  | Pt 40 | 5                |
|  | Pt 40 | 3                |
|  | Pt 40 | 4                |
|  | Pt 40 | 12               |
|  | Pt 40 | 13               |
|  | Pt 40 | 18               |
|  | Pt 40 | 9                |



LYNLEY PARK SUBDIVISION, OMOKOROA


LANDSCAPE MITIGATION PLAN - AMENDED PLAN

SOUTHERN ESCARPMENT, LOT 24

SCALE: 1:500 N/A

31 AUGUST 2005

SHEET ONE




▷ AUCKLAND 8 Waiuku Rd, New Market  
 09 524 7029  
 ▷ HAMILTON 310 Trafalgar St  
 07 833 205  
 ▷ TE KŌHĀTŪ 88 Teasdale St  
 07 871 6144  
 ▷ WAIKANAHA Cnr Brownlie & Dunganon Sts  
 03 443 5577

# Lynley Park Development SUBSOIL DRAINAGE

Durham Properties Ltd

| Issue    | Description                     | Date    |
|----------|---------------------------------|---------|
| AB       | AS-BUILT                        | 03/2006 |
| AB1      | Added planting restriction line | 04/2006 |
| Designed | Drawn                           | Checked |
|          |                                 | Date    |

|         |       |          |         |
|---------|-------|----------|---------|
| Scale:  | 1:500 | Date:    | 03/2006 |
| Job No: | D1176 | Page No: | 2 of 5  |
| Rev:    | AB1   |          |         |




▲ AUGLAND, 8 Marulan Rd, New Market  
 ▲ 09 524 7028  
 ▲ HAMILTON, 310 Trafalgar St  
 ▲ 07 835 2051  
 ▲ TE ANAU, 88 Teasdale St  
 ▲ 07 871 6144  
 ▲ WAIKATO, 577 Brownlie & Dargaville St  
 ▲ 03 443 5577

# Lynley Park Development SUBSOIL DRAINAGE

Durham Properties Ltd

| Issue    | Description                     | Date    |
|----------|---------------------------------|---------|
| AB       | AS-BUILT                        | 03/2006 |
| AB1      | Added planting restriction line | 04/2006 |
| Designed | Checked                         | Date    |
| Drawn    |                                 |         |

|         |          |
|---------|----------|
| Scale:  | Date:    |
| 1:500   | 03/2006  |
| Job No: | Page No: |
| D1176   | 3 of 5   |
|         | Rev:     |
|         | AB1      |



LEGEND:

Planting restriction line  
(5m from centreline of business drain)



▲ AUCKLAND 8 Manukau Rd, New Market  
 09 524 9029  
 ▼ HAMILTON 310 Tairāwhiti St  
 07 837 2057  
 ▼ TE ANAU 88 Tekeapa St  
 07 871 8144  
 ▼ WAIKATO Cnr Brownson & Dunganon Sts  
 03 443 5577

Lynley Park Development  
SUBSOIL DRAINAGE

Durham Properties Ltd

| Issue    | Description                     | Date    |
|----------|---------------------------------|---------|
| AB       | AS-BUILT                        | 03/2006 |
| AB1      | Added planting restriction line | 04/2006 |
| Designed |                                 |         |
| Drawn    |                                 |         |
| Checked  |                                 |         |
| Date     |                                 |         |

|         |       |          |         |
|---------|-------|----------|---------|
| Scale:  | 1:500 | Date:    | 03/2006 |
| Job No: | D1176 | Page No: | 4 of 5  |
| Rev:    | AB1   |          |         |

LEGEND:

Planting restriction line  
(5m from centreline of surface drain)

---



> AUCKLAND 8 Karamou Rd, New Market  
 > 09 524 7029  
 > HAMILTON 310 Tindem St  
 > 07 839 3031  
 > CHRISTCHURCH 88 Treadle St  
 > 07 877 8144  
 > WAIKATO Cor. Brownson & Dargavon Sts  
 > 03 443 5577

Lynley Park Development  
SUBSOIL DRAINAGE

Durham Properties Ltd

| Issue    | Description                     | Date    |
|----------|---------------------------------|---------|
| AB       | AS-BUILT                        | 03/2006 |
| AB1      | Added planting restriction line | 04/2006 |
| Designed | Checked                         | Date    |
| Drawn    |                                 |         |

|         |          |
|---------|----------|
| Scale:  | Date:    |
| 1:500   | 03/2006  |
| Job No: | Page No: |
| D1176   | 5 of 5   |
|         | Rev:     |
|         | AB1      |

