

Head Office Barkes Corner, 1484 Cameron Road, Greerton, Tauranga Private Bag 12803, Tauranga Mail Centre, Tauranga 3143 Ph 07 571 8008 (24 hours)

Freephone 0800 WBOPDC \* 0800 926 732 Email: <a href="mailto:swimmingpool@westernbay.govt.nz">swimmingpool@westernbay.govt.nz</a> Website: <a href="https://www.westernbay.govt.nz">www.westernbay.govt.nz</a>

## **Swimming Pool Fence Inspection**

**Building Act 2004, section 162D** 

Inspection Details		
Property address: BC70611	CCC UNISSUED 23 NOV 2010	Owner name: STANWICK ORCHARDS LIMITED
Inspection Date: 04/03/202	2	Reference: SPI220214269
Premise App ID: 9856	Parcel 1045/70	Is this Booking a Re-Inspection? NO
Could the inspection proceed	ed? Yes	
Inspection Outcome	n full for fail points that require	action

spection Outcome lease read this report in full for fail points that require action	
Inspection Pass/Fail?	Pass
Comments:	N/A
Reinspection Required?	No
Next Inspection Due:	N/A
Inspector signature: (36 kb)	
Inspector:	Michelle Horscroft
Signed Date and Time:	2022-03-04T13:34

Gates	
Are there any gates	Yes

Number of gates	2
Opens outwards away from pool	Pass
Clear of any obstruction	Pass
Minimum height 1200mm	Pass
Maximum clearance of 100mm under gate	Pass
Gate self closes when opened from any position	Pass
Gate self latches	Pass
Durable & does not allow lifting, dropping or accidental releasing of catch	N/A
Outside latch minimum 1500mm high	Pass
Latch cannot be released from outside by a thin implement	N/A
Any climbable diagonals less than 60 degrees are screened	N/A
Internal latch	N/A
Double gate	N/A
Gates Comments	N/A

**Gates Photos** 








Fence / Barrier	
Encloses immediate pool area and does not contain anything not used in relation to the pool e.g. clothesline, play equipment, vegetable garden	Pass
Minimum height 1200mm	Pass
Maximum clearance of 100mm under fence	Pass
Maximum 100mm between verticals	Pass
Any outside horizontals/steps min 900mm apart top to top	N/A
No projections or gaps greater than 10mm that can be used as hand/foot holds	Pass
Climbable diagonals less than 60 degrees are screened/inaccessible from the outside	N/A
Fence/Barrier secure and durable	Pass
Perforated material, mesh or trellis	N/A
Fence / Barrier Comments	N/A

Fence / Barrier Photos



Fence / Barrier Photos





R1200mm Clear Zone

No ground features or climbable objects outside the pool Pass barrier within 1200mm radius from the top of barrier that would assist a child in climbing **R1200mm Clear Zone - Comments** N/A

## 300mm Clear Zone If open paling fencing ensure no ground features or objects Pass inside the pool area 300mm parallel to the fence 300mm Clear Zone - Comments N/A

Is a building or retaining wall forming a pool barrier	No

Windows	
Windows	N/A

Back Flow Device	
Back Flow	N/A

Other Comments	
Other Comments	N/A
Other Photos	



## **Overall Immediate Pool Area**

**Building Barriers**